

**Alabama Department of Transportation
Proposal Item Summary**

017. ACOA61040-ATRP(011)

DALLAS COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 10.00

for constructing the Planing, Resurfacing, and Traffic Stripe on Lapsley Street from the intersection of Minter Avenue to the intersection of 1st Avenue and on Summerfield Road from the intersection of 1st Avenue to the intersection of Woodrow Avenue in Selma. Length 1.690 mi.

The Bracket Estimate on this project is from \$917,014 to \$1,120,795.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	4,362	SQYD	Removing Concrete Sidewalk
206C010	401	SQYD	Removing Concrete Driveway
405A000	1,678	Gal	Tack Coat
407B000	4	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	33,940	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A341	2,816	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B639	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B643	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
618A000	4,219	SQYD	Concrete Sidewalk, 4" Thick
618B003	401	SQYD	Concrete Driveway, 6" Thick (Includes Wire Mesh)
621C036	13	Each	Inlets, Type S1 Or S3 (1 Wing) (Modified)
641S500	3	Each	Valve Box Reset
645K500	3	Each	Manhole Frame And Cover Reset
650A000	1,614	CUYD	Topsoil
654A000	4,840	SQYD	Solid Sodding
659C008	723	SQYD	Erosion Control Product, Type C10
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665G000	50	Each	Sand Bags
665J002	300	LF	Silt Fence
665O001	300	LF	Silt Fence Removal
665Q002	10	LF	Wattle
674A000	500	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 48,000.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B063	228	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	167	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	5	Mile	Solid Temporary Traffic Stripe
703A002	6,929	SQFT	Traffic Control Markings, Class 2, Type A
703B002	68	SQFT	Traffic Control Legends, Class 2, Type A
703D001	6,929	SQFT	Temporary Traffic Control Markings
705A030	10	Each	Pavement Markers, Class A-H, Type 2-C
705A031	6	Each	Pavement Markers, Class A-H, Type 1-A

Item No.	Quantity	Units	Description
705A037	192	Each	Pavement Markers, Class A-H, Type 2-D
710A115	88	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710A126	236	SQFT	Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B021	624	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
730H001	2,240	LF	Loop Wire
730I001	100	LF	Loop Detector Lead-In-Cable
740B000	837	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	125	Each	Cones (36 Inches High)
740F002	4	Each	Barricades, Type III
740M001	125	Each	Ballast For Cone