

**Alabama Department of Transportation
Proposal Item Summary**

032. NH-0053(581)

MADISON COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 6.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-53 from north of the junction of Taurus Drive in Harvest to the Limestone County Line. Length 7.830 mi.

The Bracket Estimate on this project is from \$2,095,139 to \$2,560,725.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity Units	Description
206D001	250 LF	Removing Guardrail
206E008	8 Each	Removing Guardrail End Anchor (All Type)
401B108	141,493 SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	23,460 Gal	Tack Coat
407B000	8 Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	141,493 SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1 Each	Material Remixing Device
410I000	1 Each	Smoothness Testing, Certified Inertial Profiler
424A356	6,368 Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	231 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	12,028 Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	436 Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424C364	450 Ton	Superpave Bituminous Concrete Base Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	16 Mile	Scoring Bituminous Pavement Surface
430B043	8,147 Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS	Mobilization
610D003	135 SQYD	Filter Blanket, Geotextile
630A001	50 LF	Steel Beam Guardrail, Class A, Type 2
630C003	4 Each	Guardrail End Anchor, Type 13
630C050	4 Each	Guardrail End Anchor, Type 20 Series
665Q002	200 LF	Wattle
666A001	1 Acre	Pest Control Treatment
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 112,000.00)
701A227	17 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	7 Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7 Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	856 LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	13 Mile	Broken Temporary Traffic Stripe
701C001	46 Mile	Solid Temporary Traffic Stripe
701G146	412 LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	412 LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	824 LF	Solid Traffic Stripe Removed (Tape)
703A002	1,643 SQFT	Traffic Control Markings, Class 2, Type A
703B002	426 SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,632 SQFT	Temporary Traffic Control Markings

Item No.	Quantity	Units	Description
705A030	248	Each	Pavement Markers, Class A-H, Type 2-C
705A032	210	Each	Pavement Markers, Class A-H, Type 1-B
705A037	632	Each	Pavement Markers, Class A-H, Type 2-D
730H001	1,350	LF	Loop Wire
730I001	1,100	LF	Loop Detector Lead-In-Cable
730K000	2	Each	Traffic Signal Junction Box
730L005	1,100	LF	2", Non-Metallic, Conduit
740B000	524	SQFT	Construction Signs
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone