

**Alabama Department of Transportation  
Proposal Item Summary**

---

**054. STPNU-0714(251)**

**BUTLER COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Widening, Resurfacing, and Traffic Stripe on CR-7 from the junction of CR-15 in Garland to the north end of the Long Creek Bridge. Length 3.495 mi.

The Bracket Estimate on this project is from \$344,335 to \$420,854.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

| <b>Item No.</b> | <b>Quantity</b> | <b>Units</b> | <b>Description</b>   |
|-----------------|-----------------|--------------|--|
| 405A000         | 2,627           | Gal          | Tack Coat  |
| 407B000         | 4               | Mile         | Joint Sealant For Hot Mix Asphalt Pavement   |
| 424A346         | 3,218           | Ton          | Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B |
| 424B700         | 416             | Ton          | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B    |
| 424C345         | 85              | Ton          | Superpave Bituminous Concrete Base Layer, Patching, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B          |
| 424C351         | 712             | Ton          | Superpave Bituminous Concrete Base Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B          |
| 600A000         | 1               | LS           | Mobilization   |
| 698A000         | 1               | LS           | Construction Fuel (Maximum Bid Limited to \$ 18,400.00)  |
| 701A030         | 7               | Mile         | Solid White, Class 2T, Type A Traffic Stripe   |
| 701A034         | 5               | Mile         | Solid Yellow, Class 2T, Type A Traffic Stripe  |
| 701A044         | 3               | Mile         | Broken Yellow, Class 2T, Type A Traffic Stripe   |
| 701C000         | 3               | Mile         | Broken Temporary Traffic Stripe  |
| 701C001         | 5               | Mile         | Solid Temporary Traffic Stripe   |
| 705A032         | 98              | Each         | Pavement Markers, Class A-H, Type 1-B  |
| 705A037         | 340             | Each         | Pavement Markers, Class A-H, Type 2-D  |
| 740B000         | 377             | SQFT         | Construction Signs   |
| 740O000         | 1               | Each         | Pilot Car  |