

**Alabama Department of Transportation
Proposal Item Summary**

062. ST-037-999-017

JEFFERSON COUNTY

Contract Time: 55 Working Days

for constructing the Planing, Resurfacing, and Traffic Stripe on Jefferson Avenue Southwest (Site 1); on 31st Street Southwest (Site 2); on Linbergh Street and Ishkooda Road (Site 3); on Barber Court/Montevallo Road Southwest (Site 4); and on Tuscaloosa Avenue (Site 5) at various locations as indicated in the plans. Length 3.474 mi.

The Bracket Estimate on this project is from \$1,637,843 to \$2,001,808.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

| Item No. | Quantity | Units | Description |
|----------|----------|-------|--|
| 206C010 | 25 | SQYD | Removing Concrete Driveway |
| 206D003 | 37 | LF | Removing Curb And Gutter |
| 210A000 | 132 | CUYD | Unclassified Excavation |
| 210D000 | 104 | CUYD | Borrow Excavation |
| 305B077 | 828 | Ton | Crushed Aggregate, Section 825, For Miscellaneous Use |
| 405A000 | 7,888 | Gal | Tack Coat |
| 407B000 | 8 | Mile | Joint Sealant For Hot Mix Asphalt Pavement |
| 408A052 | 61,806 | SQYD | Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick) |
| 410H000 | 2 | Each | Material Remixing Device |
| 424A361 | 6,583 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424A370 | 752 | Ton | Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B655 | 4,800 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B658 | 1,000 | Ton | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B685 | 5 | Ton | Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D |
| 450A001 | 560 | SQYD | Plain Cement Concrete Pavement, 10 Inches Thick |
| 600A000 | 1 | LS | Mobilization |
| 618B000 | 25 | SQYD | Concrete Driveway, 4" Thick |
| 623C000 | 37 | LF | Combination Curb & Gutter, Type C |
| 650A000 | 55 | CUYD | Topsoil |
| 654A000 | 488 | SQYD | Solid Sodding |
| 665A000 | 2 | Acre | Temporary Seeding |
| 665B001 | 6 | Ton | Temporary Mulching |
| 665G000 | 645 | Each | Sand Bags |
| 665J002 | 1,325 | LF | Silt Fence |
| 665O001 | 1,325 | LF | Silt Fence Removal |
| 665Q002 | 900 | LF | Wattle |
| 698A000 | 1 | LS | Construction Fuel (Maximum Bid Limited to \$ 94,000.00) |
| 701A227 | 7 | Mile | Solid White, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A230 | 9 | Mile | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A239 | 4 | Mile | Broken White, Class 2, Type A Traffic Stripe (5" Wide) |
| 701A244 | 1 | Mile | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide) |
| 701B207 | 915 | LF | Dotted, Class 2, Type A Traffic Stripe (5" Wide) |
| 701C000 | 8 | Mile | Broken Temporary Traffic Stripe |
| 701C001 | 21 | Mile | Solid Temporary Traffic Stripe |

| Item No. | Quantity | Units | Description |
|----------|----------|-------|--|
| 701G142 | 1,280 | LF | Broken White, Class W, Type A Traffic Stripe (5" Wide) |
| 701G146 | 1,280 | LF | Solid White, Class W, Type A Traffic Stripe (5"Wide) |
| 701G154 | 1,280 | LF | Solid Yellow, Class W, Type A Traffic Stripe (5" Wide) |
| 701H000 | 1,280 | LF | Solid Traffic Stripe Removed (Paint) |
| 701H005 | 1,280 | LF | Broken Traffic Stripe Removed (Paint) |
| 703A002 | 3,851 | SQFT | Traffic Control Markings, Class 2, Type A |
| 703B002 | 815 | SQFT | Traffic Control Legends, Class 2, Type A |
| 703D001 | 3,173 | SQFT | Temporary Traffic Control Markings |
| 703H000 | 233 | SQFT | Specialty Traffic Control Markings |
| 705A030 | 134 | Each | Pavement Markers, Class A-H, Type 2-C |
| 705A031 | 321 | Each | Pavement Markers, Class A-H, Type 1-A |
| 705A032 | 92 | Each | Pavement Markers, Class A-H, Type 1-B |
| 705A037 | 502 | Each | Pavement Markers, Class A-H, Type 2-D |
| 705A038 | 65 | Each | Pavement Markers, Class A-H, Type 2-E |
| 730H001 | 11,929 | LF | Loop Wire |
| 740B000 | 2,227 | SQFT | Construction Signs |
| 740D000 | 150 | Each | Channelizing Drums |
| 741C010 | 3 | Each | Portable Sequential Arrow And Chevron Sign Unit |
| 742A001 | 4 | Each | Portable Changeable Message Sign, Type 2 |