

**Alabama Department of Transportation
Proposal Item Summary**

014. ACBR58549-ATRP(006) & ACBR58546-ATRP(006)

CRENSHAW COUNTY

Contract Time: 100 Working Days

DBE Goal Percent: 2.00

for constructing the Bridge Replacement and Approaches on CR-59 (Lapine Highway) over Dry Creek and Dry Creek Tributary northwest of Petry. Length 0.193 mi.

The Bracket Estimate on this project is from \$1,218,583 to \$1,340,937.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$15.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206A000	1	LS	Removal Of Old Bridge, Station 711+57.43
206A001	1	LS	Removal Of Old Bridge, Station 680+97.16
210A000	295	CUYD	Unclassified Excavation
210D021	3,300	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	300	CUYD	Structure Excavation
214B001	210	CUYD	Foundation Backfill, Commercial
230A000	8	RBST	Roadbed Processing
301A025	1,905	SQYD	Crushed Aggregate Base Course, Type B, Road Mixed, 6" Compacted Thickness
401A000	1,905	SQYD	Bituminous Treatment A
424A341	155	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
502A000	29,156	LB	Steel Reinforcement
505G006	12	Each	Pile Points (Type B, 12")
505G007	30	Each	Pile Points (Type B, 14")
505M002	540	LF	Steel Piling Furnished And Driven (HP 12x53)
505M104	1,350	LF	Steel Piling Furnished And Driven (HP 14x73) (Galvanized)
508A000	272	LB	Structural Steel
510A007	15	CUYD	Bridge Substructure Concrete
511A000	88	Each	Elastomeric Bearing Type 1
512B004	6	Each	Precast Concrete Intermediate Bent Caps, 2'-0" Wide By 2'-0" Deep By 31'-6" Long
512C017	42	Each	Precast Concrete Type 1 Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512C025	14	Each	Precast Concrete Type 2C Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512D025	10	Each	Precast Concrete Barrier Rail Intermediate Section, 39'-11" Long
512D030	4	Each	Precast Concrete Barrier Rail End Section, 39'-11 3/8" Long
524A010	138	CUYD	Culvert Concrete
600A000	1	LS	Mobilization
610C001	580	Ton	Loose Riprap, Class 2
610D003	855	SQYD	Filter Blanket, Geotextile
630A001	250	LF	Steel Beam Guardrail, Class A, Type 2
630C003	4	Each	Guardrail End Anchor, Type 13
630C050	8	Each	Guardrail End Anchor, Type 20 Series
650A000	270	CUYD	Topsoil
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665J002	2,295	LF	Silt Fence
665L000	200	LF	Floating Basin Boom
665Q002	160	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 55,000.00)

Item No.	Quantity	Units	Description
740B000	528	SQFT	Construction Signs
740F002	22	Each	Barricades, Type III
740I002	11	Each	Warning Lights, Type B