

**Alabama Department of Transportation
Proposal Item Summary**

020. ACBRZ59493-ATRP(012)

JEFFERSON COUNTY

Contract Time: 35 Working Days

DBE Goal Percent: 3.00

for constructing the Bridge Replacement on 23rd Street North in Bessemer. Length 0.021 mi.

The Bracket Estimate on this project is from \$201,507 to \$246,286.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206B000	1	LS	Removal Of Old Box Culvert, Station 1+49.72
206D011	36	LF	Removing Fence
206E006	1	Each	Removing Trees
210A000	134	CUYD	Unclassified Excavation
210D021	50	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214A000	227	CUYD	Structure Excavation
214B001	340	CUYD	Foundation Backfill, Commercial
230A000	1	RBST	Roadbed Processing
301A020	249	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 8" Compacted Thickness
401A043	249	SQYD	Bituminous Treatment AE
405A000	50	Gal	Tack Coat
424A340	20	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	27	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
502A000	18,216	LB	Steel Reinforcement
524A010	114	CUYD	Culvert Concrete
600A000	1	LS	Mobilization
610C001	33	Ton	Loose Riprap, Class 2
610D003	369	SQYD	Filter Blanket, Geotextile
630A001	97	LF	Steel Beam Guardrail, Class A, Type 2
630C001	2	Each	Guardrail End Anchor, Type 8
630C070	2	Each	Guardrail End Anchor, Type 10 Series
637A001	14	LF	Fence Reset (Includes All Types)
650A000	19	CUYD	Topsoil
654A001	167	SQYD	Solid Sodding (Bermuda)
659C002	200	SQYD	Erosion Control Product, Type S2
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665E000	100	SQYD	Polyethylene
665G000	50	Each	Sand Bags
665J002	250	LF	Silt Fence
665N000	50	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	250	LF	Silt Fence Removal
665Q002	150	LF	Wattle
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 8,000.00)
740B000	129	SQFT	Construction Signs
740D000	20	Each	Channelizing Drums
740F002	8	Each	Barricades, Type III

Item No.	Quantity	Units	Description
740I002	4 Each		Warning Lights, Type B