

**Alabama Department of Transportation  
Proposal Item Summary**

**032. ACOA65584-ATRP(008)**

**WALKER COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing (Scrub Seal), Traffic Signals, and Traffic Stripe on Viking Drive from the intersection of 20th Avenue East to the junction of SR-5 (US-78) in Jasper. Length 0.753 mi.

The Bracket Estimate on this project is from \$388,663 to \$475,033.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
305B071	500	Ton	Coarse Aggregate, Section 801, For Miscellaneous Use
404G001	13,608	SQYD	Pavement Surfacing (Scrub Seal)
405A000	906	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A360	1,150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B658	250	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	1,413	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	167	SQYD	Filter Blanket, Geotextile
650A000	10	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665P005	9	Each	Inlet Protection, Stage 3 Or 4
665Q002	250	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 20,900.00)
701A227	2	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	2	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	76	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C001	7	Mile	Solid Temporary Traffic Stripe
703A002	226	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	148	SQFT	Temporary Traffic Control Markings
705A030	8	Each	Pavement Markers, Class A-H, Type 2-C
705A037	52	Each	Pavement Markers, Class A-H, Type 2-D
710A115	23	SQFT	Class 4, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type III Or Type IV Background)
710A126	4	SQFT	Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B021	56	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)
710C000	1	LS	Removal Of Existing Roadway Signs
730C000	1	LS	Furnishing And Installing Traffic Control Unit ( Viking Drive at Jones Dairy Road)
730E000	4	Each	Metal Traffic Signal Pole Foundation
730G001	4	Each	Metal Traffic Signal Strain Pole

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
730H001	1,200	LF	Loop Wire
730I001	950	LF	Loop Detector Lead-In-Cable
730J010	4	Each	Vehicle Loop Detector
730K000	5	Each	Traffic Signal Junction Box
730L002	60	LF	1", Metallic, Conduit
730L003	50	LF	1", Non-Metallic, Conduit
730L005	550	LF	2", Non-Metallic, Conduit
730N010	4	Each	Luminaire Extension Assembly, 12 foot
730P022	8	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730R022	1	Each	Controller Assembly, Type III, 8 Phase
740B000	186	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone
740O000	1	Each	Pilot Car