

**Alabama Department of Transportation
Proposal Item Summary**

036. ERPR-9010(141)

WINSTON COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 2.00

for constructing the Roadway Culvert Replacement (Grading, Drainage, Base, Pavement, and Traffic Stripe) on CR-12 over a Tributary to Lewis Smith Lake east of the junction of CR-207 southeast of Ardell. Length 0.085 mi.

The Bracket Estimate on this project is from \$291,485 to \$321,129.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
210A000	119	CUYD	Unclassified Excavation
210D021	2,542	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
214B002	320	CUYD	Foundation Backfill, Commercial (ALDOT #467)
230A000	5	RBST	Roadbed Processing
246A000	237	CUYD	Gabions
301A012	1,100	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,050	SQYD	Bituminous Treatment A
405A000	55	Gal	Tack Coat
407B000	1	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	75	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	132	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	53	Ton	Aggregate Surfacing (1" Down, Crusher Run)
531D000	1	LS	Corrugated Metal Structural Plate Arch
600A000	1	LS	Mobilization
610D003	300	SQYD	Filter Blanket, Geotextile
630A001	125	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665J002	1,200	LF	Silt Fence
665O001	1,200	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 11,500.00)
701G249	940	LF	Solid White, Class 2, Type A Traffic Stripe
701G263	940	LF	Solid Yellow, Class 2, Type A Traffic Stripe
740B000	109	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B