

**Alabama Department of Transportation  
Proposal Item Summary**

**037. ERPR-9010(981)**

**RUSSELL COUNTY**

Contract Time: 75 Working Days

DBE Goal Percent: 2.00

for constructing the Slope Repair (Front Slope Failure) on SR-165 at MP 15.000 (Southbound Roadway) southwest of Holy Trinity.

The Bracket Estimate on this project is from \$732,368 to \$806,101.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity Units	Description
201A002	1 LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
210A000	8,000 CUYD	Unclassified Excavation
210D023	6,500 CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-4(0) Or Better)
219A000	6,000 Ton	Rock Buttress For Landslide Correction
219B001	15 LF	Special Underdrain 8 Inch Diameter
219C003	1,470 SQYD	Special Filter Blanket, Geotextile
243A021	3,800 SQYD	Geosynthetic Reinforcement For Reinforced Slopes, Type 2
305B077	125 Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401A000	415 SQYD	Bituminous Treatment A
405A000	95 Gal	Tack Coat
408A052	80 SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
424A364	40 Ton	Superpave Bituminous Concrete Wearing Surface Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	50 Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B684	145 Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1 LS	Mobilization
605B000	1 Each	Special Underdrain Outlet, Type A
610D003	250 SQYD	Filter Blanket, Geotextile
630A033	292 LF	Steel Beam Guardrail, Class A, Type 2 (7'-0" Post)
630C050	2 Each	Guardrail End Anchor, Type 20 Series
650A000	200 CUYD	Topsoil
652A100	1 Acre	Seeding
654A001	100 SQYD	Solid Sodding (Bermuda)
656A010	1 Acre	Mulching
659C002	250 SQYD	Erosion Control Product, Type S2
665A000	1 Acre	Temporary Seeding
665B001	3 Ton	Temporary Mulching
665E000	2,000 SQYD	Polyethylene
665F000	200 Each	Hay Bales
665J002	600 LF	Silt Fence
665N000	250 Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	600 LF	Silt Fence Removal
665Q002	100 LF	Wattle
680A001	1 LS	Geometric Controls
698A000	1 LS	Construction Fuel (Maximum Bid Limited to \$ 34,000.00)
701A227	1 Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A239	1 Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701C000	1 Mile	Broken Temporary Traffic Stripe

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
701C001	1	Mile	Solid Temporary Traffic Stripe
705A030	5	Each	Pavement Markers, Class A-H, Type 2-C
726A000	450	LF	Portable Concrete Safety Barriers, Type 6
740B000	257	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740M001	100	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2