



ALABAMA DEPARTMENT OF TRANSPORTATION

1409 Coliseum Boulevard, Montgomery, Alabama 36110
Bureau of Office Engineer
Plans and Proposals Section
Telephone: 334-242-6444 FAX: 334-264-7976
www.dot.state.al.us




Kay Ivey
Governor

John R. Cooper
Transportation Director

September 9, 2019

MEMORANDUM

To: Proposal Holders

From: Bryan E. Nichols
Assistant Bureau Chief 

Subject: STPPC-ACBR59582-ATRP (011)
Russell County
September 27, 2019 Letting

Enclosed are the Revised Proposal Sheet Nos. 1-7 for the above referenced project.

Prospective bidders are advised to download the amended. ebs files from the ALDOT website or the Bid Express website.

It is the bidder's responsibility to notify vendors, suppliers and subcontractors of this change.

This change must be incorporated into your proposal and used in the preparation of your bid. Failure to do so may cause your bid to be considered irregular and non-responsive and may result in the automatic rejection of your bid.

BEN/jss

Attachment

cc: Mr. Steve Graben, P.E.



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
SECTION: 0001		Total				
0010	201A002 Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 4 Acres)	LUMP SUM	LUMP SUM			
0020	206A000 Removal Of Old Bridge, Station 105+63.09	LUMP SUM	LUMP SUM			
0030	206A001 Removal Of Old Bridge, Station 105+81.94	LUMP SUM	LUMP SUM			
0040	206B000 Removal Of Old Box Culvert, Station 12+93.00	LUMP SUM	LUMP SUM			
0050	206C010 Removing Concrete Driveway	21.000 SQYD				
0060	206D000 Removing Pipe	124.000 LF				
0070	206D011 Removing Fence	52.000 LF				
0080	206D030 Removing Utility Lines	750.000 LF				
0090	206E000 Removing Headwalls	8.000 Each				
0100	206E003 Removing Manholes	1.000 Each				
0110	210A000 Unclassified Excavation	2,650.000 CUYD				
0120	210D011 Borrow Excavation (A4 Or Better)	14,132.000 CUYD				
0130	214A000 Structure Excavation	166.000 CUYD				
0140	214B001 Foundation Backfill, Commercial	63.000 CUYD				
0150	230A000 Roadbed Processing	14.000 RBST				
0160	260A002 Cement Mortar Flowable Backfill, Mix 3	40.000 CUYD				
0170	301A012 Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness	5,061.000 SQYD				
0180	401A000 Bituminous Treatment A	4,865.000 SQYD				



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0190	405A000 Tack Coat	1,140.000 Gal				
0200	407B000 Joint Sealant For Hot Mix Asphalt Pavement	1.000 Mile				
0210	424A360 Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D	346.000 Ton				
0220	424A369 Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D	9.000 Ton				
0230	424B650 Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D	512.000 Ton				
0240	424B661 Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D	15.000 Ton				
0250	424B680 Superpave Bituminous Concrete Lower Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D	497.000 Ton				
0260	424C360 Superpave Bituminous Concrete Base Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D	585.000 Ton				
0270	430B000 Aggregate Surfacing (ALDOT #467 Or #57)	35.000 Ton				
0280	450B000 Reinforced Cement Concrete Bridge End Slab	228.000 SQYD				
0290	502A000 Steel Reinforcement	65,994.000 LB				
0300	502B000 Steel Reinforcement For Bridge Superstructure, Station 105+30.00, Approximately 44,700 Pounds	LUMP SUM	LUMP SUM			
0310	506A005 Drilled Shaft Excavation, 3'-6" Diameter	68.000 LF				
0320	506B002 Special Drilled Shaft Excavation, 3'-6" Diameter	86.000 LF				
0330	506C041 Drilled Shaft Construction, 3'-6" Diameter, Class DS1 Concrete	154.000 LF				
0340	506F000 Permanent Drilled Shaft Casing, 3'-6" Diameter	56.000 LF				



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0350	506G001 Crosshole Sonic Logging, 3'-6" Diameter	6.000 Each				
0360	508A000 Structural Steel	6,000.000 LB				
0370	510A007 Bridge Substructure Concrete	168.000 CUYD				
0380	510C051 Bridge Concrete Superstructure, Station 105+30.00, Approximately 180 Cubic Yards	LUMP SUM	LUMP SUM			
0390	510E000 Grooving Concrete Bridge Decks	643.000 SQYD				
0400	511A050 Elastomeric Bearing Type 2 (Mark B1)	48.000 Each				
0410	513B003 Pretensioned-Prestressed Concrete Girders, Type I (Specialty Item)	930.000 LF				
0420	524A010 Culvert Concrete	96.000 CUYD				
0430	535A080 18" Side Drain Pipe (Class 3 R.C.)	208.000 LF				
0440	600A000 Mobilization	LUMP SUM	LUMP SUM			
0450	602A000 Right Of Way Markers	12.000 Each				
0460	610C001 Loose Riprap, Class 2	1,151.000 Ton				
0470	610D003 Filter Blanket, Geotextile	1,519.000 SQYD				
0480	618B003 Concrete Driveway, 6" Thick (Includes Wire Mesh)	21.000 SQYD				
0490	619A101 18" Side Drain Pipe End Treatment, Class 1	8.000 Each				
0500	630A001 Steel Beam Guardrail, Class A, Type 2	263.000 LF				
0510	630C003 Guardrail End Anchor, Type 13	3.000 Each				
0520	630C080 Guardrail End Anchor, Type 20 Series (MASH)	3.000 Each				
0530	641A514 1 Inch Copper Water Service Line Laid	84.000 LF				



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0540	641A612 6 Inch Ductile Iron Water Main Laid	20.000 LF				
0550	641A614 8 Inch Ductile Iron Water Main Laid	880.000 LF				
0560	641A684 8 Inch Ductile Iron Water Main Laid (Restrained Joint)	40.000 LF				
0570	641C500 Ductile Iron Fittings	730.000 LB				
0580	641D500 Fire Hydrant	2.000 Each				
0590	641J516 6 Inch Gate Valve With Box	1.000 Each				
0600	641J518 8 Inch Gate Valve With Box	2.000 Each				
0610	641L500 Concrete for Water Mains (Thrust Blocks)	50.000 CUYD				
0620	641M512 6 Inch Retainer Gland	3.000 Each				
0630	641M514 8 Inch Retainer Gland	15.000 Each				
0640	641O520 8 Inch x 8 Inch Tapping Valve And Sleeve	2.000 Each				
0650	641R515 1 Inch Water Meter And Box Reset	2.000 Each				
0660	641T512 8 Inch Line Stop	2.000 Each				
0670	641V100 Double Check Valve Assembly with Vault	1.000 Each				
0685	645A562 24 Inch P.V.C. Sanitary Sewer Gravity Pipe Laid	320.000 LF				
0690	645F545 24 Inch Abandon Existing Sanitary Sewer	332.000 LF				
0700	645M500 Connection To Existing Manhole	2.000 Each				
0710	645N500 Abandon Existing Manhole	1.000 Each				
0720	649A550 18 Inch Steel Encasement Pipe, Type 1 Installation	70.000 LF				



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0730	649A670 36 Inch Steel Encasement Pipe, Type 2 Installation	180.000 LF				
0740	650A000 Topsoil	1,170.000 CUYD				
0750	652A100 Seeding	2.000 Acre				
0760	652C000 Mowing	2.000 Acre				
0770	656A010 Mulching	2.000 Acre				
0780	659C004 Erosion Control Product, Type C2	128.000 SQYD				
0790	659C005 Erosion Control Product, Type C4	1,275.000 SQYD				
0800	665A000 Temporary Seeding	2.000 Acre				
0810	665B001 Temporary Mulching	6.000 Ton				
0820	665C010 Temporary Pipe	45.000 LF				
0830	665D001 Temporary Pipe End Treatment	4.000 Each				
0840	665F000 Hay Bales	374.000 Each				
0850	665G000 Sand Bags	10.000 Each				
0860	665I000 Temporary Riprap, Class 2	90.000 Ton				
0870	665J002 Silt Fence	5,831.000 LF				
0880	665N000 Temporary Coarse Aggregate,ALDOT Number 1	340.000 Ton				
0890	665N001 Temporary Coarse Aggregate,ALDOT Number 4	18.000 Ton				
0900	665O001 Silt Fence Removal	5,831.000 LF				
0910	665Q002 Wattle	102.000 LF				



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
0920	666A001 Pest Control Treatment	2.000 Acre				
0930	680A001 Geometric Controls	LUMP SUM	LUMP SUM			
0940	698A000 Construction Fuel (Maximum Bid Limited to \$ 139,000.00)	LUMP SUM	LUMP SUM			
0950	701B207 Dotted, Class 2, Type A Traffic Stripe (5" Wide)	113.000 LF				
0960	701G146 Solid White, Class W, Type A Traffic Stripe (5" Wide)	240.000 LF				
0970	701G154 Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)	240.000 LF				
0980	701G253 Solid White, Class 2, Type A Traffic Stripe (5" Wide)	3,335.000 LF				
0990	701G265 Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)	2,970.000 LF				
1000	703A002 Traffic Control Markings, Class 2, Type A	542.000 SQFT				
1010	703A011 Traffic Control Markings, Class W, Type A	307.000 SQFT				
1020	703B002 Traffic Control Legends, Class 2, Type A	23.000 SQFT				
1030	703B011 Traffic Control Legends, Class W, Type A	23.000 SQFT				
1040	705A030 Pavement Markers, Class A-H, Type 2-C	19.000 Each				
1050	705A037 Pavement Markers, Class A-H, Type 2-D	43.000 Each				
1060	710A160 Class 10 Aluminum Flat Sign Panels 0.08" Thick (Type XI Background)	15.000 SQFT				
1070	710A170 Class 4, Aluminum Flat Sign Panels 0.08" Thick (Type IV Background)	7.000 SQFT				
1080	710B021 Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel)	42.000 LF				
1090	710C000 Removal Of Existing Roadway Signs	LUMP SUM	LUMP SUM			



Schedule of Items

REVISED: 9/9/19

CONTRACT ID: 20190927050 PROJECT(S): STPPC-ACBR59582-ATRP(011)

THE FOLLOWING ITEMS SHALL BE IN ACCORDANCE WITH THE ALABAMA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS, 2018 EDITION, EXCEPT AS MODIFIED BY SPECIAL PROVISIONS HERETO ATTACHED.

Proposal Line Number	Item ID Description	Approximate Quantity and Units	Unit Price		Bid Amount	
			Dollars	Cents	Dollars	Cents
1100	711A000 Roadway Sign Relocation	LUMP SUM	LUMP SUM			
1110	740B000 Construction Signs	314.000 SQFT				
1120	740C000 Special Construction Signs	56.000 SQFT				
1130	740D000 Channelizing Drums	50.000 Each				
1140	740F002 Barricades, Type III	14.000 Each				
1150	740I002 Warning Lights, Type B	7.000 Each				
1160	742A001 Portable Changeable Message Sign, Type 2	2.000 Each				
Section: 0001			Total:			
			Total Bid:			

For Information Only
Not to Be Used
For Submission of Bid