

**Alabama Department of Transportation
Proposal Item Summary**

002. APDF-IMF-0004(530)

WALKER COUNTY

Contract Time: 180 Working Days

DBE Goal Percent: 5.00

for constructing the Ultimate Paving, Guardrail Installation, and Traffic Stripe on I-22 (Corridor X) from the SR-118 Interchange (MP 51.830) to the SR-118 Overpass Ramps (MP 57.440) west of Jasper. Length 5.535 mi.

The Bracket Estimate on this project is from \$14,818,281 to \$18,111,232.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$32.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	4,625	LF	Removing Guardrail
206E008	50	Each	Removing Guardrail End Anchor (All Type)
210D000	17,500	CUYD	Borrow Excavation
405A000	43,362	Gal	Tack Coat
407B000	28	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A053	467,540	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
408A054	620	SQYD	Planing Existing Pavement (Approximately 3.10" Thru 4.0" Thick)
410C000	1	Each	Contractor Retained Profilograph
410H000	1	Each	Material Remixing Device
423A003	30,180	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
423B002	30,415	Ton	Stone Matrix Asphalt Binder Layer, 3/4" Maximum Aggregate Size
424A360	18,565	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B581	84,844	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range E
424B584	2,390	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL E
424B650	12,156	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	22	Mile	Scoring Bituminous Pavement Surface
430B043	1,000	Ton	Aggregate Surfacing (1" Down, Crusher Run)
534A000	145	Each	Cleaning Pipe Underdrain Outlets
600A000	1	LS	Mobilization
603A002	1	Each	Furnishing Type 3 Field Office
605B000	10	Each	Special Underdrain Outlet, Type A
630A001	6,138	LF	Steel Beam Guardrail, Class A, Type 2
630C001	15	Each	Guardrail End Anchor, Type 8
630C003	10	Each	Guardrail End Anchor, Type 13
630C070	25	Each	Guardrail End Anchor, Type 10 Series
650A000	1,500	CUYD	Topsoil
652A100	15	Acre	Seeding
654A001	35,041	SQYD	Solid Sodding (Bermuda)
656A010	15	Acre	Mulching
665A000	15	Acre	Temporary Seeding
665B001	45	Ton	Temporary Mulching
665G000	150	Each	Sand Bags
665J002	20,750	LF	Silt Fence

Item No.	Quantity	Units	Description
665O001	20,750	LF	Silt Fence Removal
665P005	86	Each	Inlet Protection, Stage 3 Or 4
665Q002	6,500	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 776,726.00)
701A087	1	Mile	Broken White, Class W, Type A Traffic Stripe (5" Wide)
701A091	1	Mile	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701A099	1	Mile	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701A227	17	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	17	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	23	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B027	918	LF	Dotted, Class W, Type A Traffic Stripe (5" Wide)
701B063	5,200	LF	Dotted, Class 2, Type A Traffic Stripe(Lane Drop 10" Wide)
701B207	5,581	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	28	Mile	Broken Temporary Traffic Stripe
701C001	36	Mile	Solid Temporary Traffic Stripe
701D005	1	Mile	Solid Traffic Stripe Removed
701D013	1	Mile	Broken Traffic Stripe Removed
701F000	25,674	LF	Dotted Temporary Traffic Stripe
701F010	9,450	LF	Dotted Temporary Traffic Stripe (Lane Drop)
701G161	2,400	LF	Broken Black, Class W, Type B Traffic Stripe (5" Wide)
703A002	17,771	SQFT	Traffic Control Markings, Class 2, Type A
703B002	662	SQFT	Traffic Control Legends, Class 2, Type A
703C000	1,500	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Paint)
703D001	17,771	SQFT	Temporary Traffic Control Markings
705A011	1,120	Each	Pavement Markers, Class C, Type 1-A
705A012	800	Each	Pavement Markers, Class C, Type 1-B
705A022	1,920	Each	Pavement Markers, Class C, Type 2-C
705A030	284	Each	Pavement Markers, Class A-H, Type 2-C
705A031	3,925	Each	Pavement Markers, Class A-H, Type 1-A
705A032	420	Each	Pavement Markers, Class A-H, Type 1-B
728A000	2	Each	Truck Mounted Impact Attenuator Unit
740B000	3,005	SQFT	Construction Signs
740C000	96	SQFT	Special Construction Signs
740D000	1,000	Each	Channelizing Drums
740E000	100	Each	Cones (36 Inches High)
740F002	4	Each	Barricades, Type III
740I002	12	Each	Warning Lights, Type B
740M001	100	Each	Ballast For Cone
741C010	4	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2
999 000	1,760	HOUR	Trainee Hours At 80 Cents Per Hour