

**Alabama Department of Transportation
Proposal Item Summary**

011. ACBR62448-ATRP(009)

FRANKLIN COUNTY

Contract Time: 80 Working Days

for constructing the Bridge Replacement on CR-23 over North Fork Creek west of Vina. Length 0.040 mi.

The Bracket Estimate on this project is from \$260,533 to \$318,430.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ \$4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 5+87.70 To 6+34.39
210A000	109	CUYD	Unclassified Excavation
210D001	155	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	839	CUYD	Structure Excavation
214B001	126	CUYD	Foundation Backfill, Commercial
230A000	3	RBST	Roadbed Processing
301A012	300	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	300	SQYD	Bituminous Treatment A
405A000	30	Gal	Tack Coat
424A340	22	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	27	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B665	33	Ton	Superpave Bituminous Concrete Lower Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	25	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	32,246	LB	Steel Reinforcement
524A010	137	CUYD	Culvert Concrete
600A000	1	LS	Mobilization
610C001	100	Ton	Loose Riprap, Class 2
610D003	104	SQYD	Filter Blanket, Geotextile
629A004	72	LF	Concrete Median Or Safety Barrier, Type 4A (Modified)
630C003	4	Each	Guardrail End Anchor, Type 13
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	60	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
659C001	145	SQYD	Erosion Control Product, Type S3
665F000	32	Each	Hay Bales
665I000	5	Ton	Temporary Riprap, Class 2
665J002	345	LF	Silt Fence
665O001	345	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 8,000.00)
701E000	516	LF	Solid Temporary Traffic Stripe
701G083	258	LF	Solid White, Class 2T, Type A Traffic Stripe
701G089	258	LF	Solid Yellow, Class 2T, Type A Traffic Stripe

Item No.	Quantity	Units	Description
705A005	4	Each	Pavement Markers, Class A, Type 2-D
740B000	99	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B