

**Alabama Department of Transportation
Proposal Item Summary**

014. ACBRZ58361-ATRP(001)

CALHOUN COUNTY

Contract Time: 60 Working Days

DBE Goal Percent: 2.00

for constructing the Bridge Replacement and Approaches on Ranch Road over an Unknown Branch northeast of Wellington. Length 0.150 mi.

The Bracket Estimate on this project is from \$623,071 to \$761,532.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 15+95.77
206D000	20	LF	Removing Pipe
210A000	130	CUYD	Unclassified Excavation
210D001	3,450	CUYD	Borrow Excavation (Loose Truckbed Measurement)
301A012	1,354	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,354	SQYD	Bituminous Treatment A
405A000	53	Gal	Tack Coat
424A340	105	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	228	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	30	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A001	80	LB	Steel Reinforcement (Grade 60)
505G003	24	Each	Pile Points (Type A, 12")
505H000	305	LF	Pilot Holes
505M002	400	LF	Steel Piling Furnished And Driven (HP 12x53)
505M011	300	LF	Steel Piling Furnished And Driven (HP 14X102)
507A000	2	Each	Wire Rope Abutment Anchor Assembly
510A000	15	CUYD	Bridge Substructure Concrete, Class A
511A000	44	Each	Elastomeric Bearing Type 1
512A014	2	Each	Precast Concrete Abutment Caps, 2'-0" Wide By 1'-8" Deep By 33'-0" Long
512B004	2	Each	Precast Concrete Intermediate Bent Caps, 2'-0" Wide By 2'-0" Deep By 31'-6" Long
512C017	18	Each	Precast Concrete Type 1 Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512C025	6	Each	Precast Concrete Type 2C Span Section, 3'-6" By 2'-0" Deep By 39'-11 3/4" Long
512D025	2	Each	Precast Concrete Barrier Rail Intermediate Section, 39'-11" Long
512D030	4	Each	Precast Concrete Barrier Rail End Section, 39'-11 3/8" Long
512E000	8	Each	Precast Concrete Abutment Panels, Type A1
512E001	8	Each	Precast Concrete Abutment Panels, Type A2
512F000	4	Each	Precast Concrete Wing Panels, Type W1
512F001	4	Each	Precast Concrete Wing Panels, Type W2
512G000	4	Each	Precast Concrete Abutment Wing Cap Panels
535A002	40	LF	24" Side Drain Pipe
600A000	1	LS	Mobilization
602A000	18	Each	Right Of Way Markers
610C001	1,310	Ton	Loose Riprap, Class 2
610D003	1,310	SQYD	Filter Blanket, Geotextile

Item No.	Quantity	Units	Description
619A102	2	Each	24" Side Drain Pipe End Treatment, Class 1
630A001	25	LF	Steel Beam Guardrail, Class A, Type 2
630C003	4	Each	Guardrail End Anchor, Type 13
630C070	4	Each	Guardrail End Anchor, Type 10 Series
650A000	750	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665F000	100	Each	Hay Bales
665J002	1,600	LF	Silt Fence
665L000	200	LF	Floating Basin Boom
665O001	1,600	LF	Silt Fence Removal
666A001	1	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 32,000.00)
701A231	1	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	1	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701C001	1	Mile	Solid Temporary Traffic Stripe
705A037	20	Each	Pavement Markers, Class A-H, Type 2-D
740B000	141	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B