

**Alabama Department of Transportation
Proposal Item Summary**

015. ACBRZ58617-ATRP(004)

ETOWAH COUNTY

Contract Time: 75 Working Days

DBE Goal Percent: 3.00

for constructing the Bridge Replacement on Pineview Avenue over Little Cove Creek 0.10 mile east of SR-1 (US-431) in Glencoe. Length 0.074 mi.

The Bracket Estimate on this project is from \$550,222 to \$672,493.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 14+13.53
206D000	46	LF	Removing Pipe
210A000	335	CUYD	Unclassified Excavation
210B000	826	CUYD	Channel Excavation
210D001	379	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	1,347	CUYD	Structure Excavation
214B001	283	CUYD	Foundation Backfill, Commercial
301A012	1,119	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,119	SQYD	Bituminous Treatment A
405A000	56	Gal	Tack Coat
424A340	65	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	128	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
502A000	65,476	LB	Steel Reinforcement
524A011	385	CUYD	Culvert Concrete (Cast In Place)
535A078	35	LF	15" Side Drain Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
602A000	10	Each	Right Of Way Markers
610C001	1,240	Ton	Loose Riprap, Class 2
610D003	1,111	SQYD	Filter Blanket, Geotextile
619A100	2	Each	15" Side Drain Pipe End Treatment, Class 1
630A001	250	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	62	CUYD	Topsoil
650B000	102	CUYD	Topsoil From Stockpiles
654A000	1,647	SQYD	Solid Sodding
665A000	1	Acre	Temporary Seeding
665B001	3	Ton	Temporary Mulching
665I000	140	Ton	Temporary Riprap, Class 2
665J002	1,466	LF	Silt Fence
665O001	1,466	LF	Silt Fence Removal
665Q002	100	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 18,000.00)
701G249	788	LF	Solid White, Class 2, Type A Traffic Stripe

Item No.	Quantity	Units	Description
701G263	788	LF	Solid Yellow, Class 2, Type A Traffic Stripe
705A037	10	Each	Pavement Markers, Class A-H, Type 2-D
740B000	161	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740F002	6	Each	Barricades, Type III
740I002	3	Each	Warning Lights, Type B