

**Alabama Department of Transportation
Proposal Item Summary**

020. ACNU58347-ATRP(002)

LOWNDES COUNTY

Contract Time: 45 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-12 (Wall Street) from the junction of CR-17 in Mosses to the junction of SR-21. Length 5.969 mi.

The Bracket Estimate on this project is from \$784,194 to \$958,459.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	4,203	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A336	2,802	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B638	175	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	7,005	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
650A000	2,627	CUYD	Topsoil
652A100	5	Acre	Seeding
656A010	5	Acre	Mulching
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 44,000.00)
701A030	12	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	7	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	5	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	5	Mile	Broken Temporary Traffic Stripe
701C001	19	Mile	Solid Temporary Traffic Stripe
701G251	275	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A004	120	SQFT	Traffic Control Markings, Class 2T, Type A
705A032	137	Each	Pavement Markers, Class A-H, Type 1-B
705A037	395	Each	Pavement Markers, Class A-H, Type 2-D
740B000	273	SQFT	Construction Signs
740O000	1	Each	Pilot Car