

**Alabama Department of Transportation  
Proposal Item Summary**

**021. ACNU59571-ATRP(016)**

**RUSSELL COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 2.00

for constructing the Resurfacing and Traffic Stripe on Various Sites as indicated in the plans. Length 21.397 mi.

The Bracket Estimate on this project is from \$2,412,136 to \$2,948,167.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity | Units | Description   |
|----------|----------|-------|---|
| 206D001  | 54       | LF    | Removing Guardrail  |
| 210D001  | 650      | CUYD  | Borrow Excavation (Loose Truckbed Measurement)  |
| 401B108  | 77,702   | SQYD  | Bituminous Treatment G (With Polymer Additive)  |
| 405A000  | 3,200    | Gal   | Tack Coat   |
| 407B000  | 6        | Mile  | Joint Sealant For Hot Mix Asphalt Pavement  |
| 409A001  | 248,673  | SQYD  | Triple Layer Bituminous Treatment   |
| 424A340  | 1,675    | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B        |
| 424A360  | 4,370    | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D        |
| 424B640  | 1,390    | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B   |
| 424B642  | 3,225    | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B |
| 424B655  | 300      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D   |
| 424B657  | 425      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D |
| 430B043  | 1,735    | Ton   | Aggregate Surfacing (1" Down, Crusher Run)  |
| 600A000  | 1        | LS    | Mobilization  |
| 630C022  | 4        | Each  | Guardrail End Anchor, Type Special  |
| 630C050  | 4        | Each  | Guardrail End Anchor, Type 20 Series  |
| 665F000  | 50       | Each  | Hay Bales   |
| 665J002  | 500      | LF    | Silt Fence  |
| 665O001  | 500      | LF    | Silt Fence Removal  |
| 698A000  | 1        | LS    | Construction Fuel (Maximum Bid Limited to \$ 126,000.00)  |
| 701A227  | 44       | Mile  | Solid White, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A230  | 35       | Mile  | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A239  | 4        | Mile  | Broken White, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A244  | 10       | Mile  | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701B207  | 2,930    | LF    | Dotted, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701C000  | 19       | Mile  | Broken Temporary Traffic Stripe   |
| 701C001  | 92       | Mile  | Solid Temporary Traffic Stripe  |
| 701G252  | 1,080    | LF    | Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)  |
| 703A002  | 8,720    | SQFT  | Traffic Control Markings, Class 2, Type A   |
| 703B002  | 544      | SQFT  | Traffic Control Legends, Class 2, Type A  |
| 703D001  | 1,696    | SQFT  | Temporary Traffic Control Markings  |
| 705A031  | 120      | Each  | Pavement Markers, Class A-H, Type 1-A   |
| 705A032  | 485      | Each  | Pavement Markers, Class A-H, Type 1-B   |

| <b>Item No.</b> | <b>Quantity</b> | <b>Units</b> | <b>Description</b>                    |
|-----------------|-----------------|--------------|---------------------------------------|
| 705A037         | 2,367           | Each         | Pavement Markers, Class A-H, Type 2-D |
| 740B000         | 1,103           | SQFT         | Construction Signs                    |
| 740O000         | 1               | Each         | Pilot Car                             |