

**Alabama Department of Transportation
Proposal Item Summary**

023. ACNU61039-ATRP(012)

AUTAUGA COUNTY

Contract Time: 35 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-16 from the junction of CR-83 to the junction of CR-1. Length 7.689 mi.

The Bracket Estimate on this project is from \$871,049 to \$1,064,616.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	8,950	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A336	4,775	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	6,040	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
600A000	1	LS	Mobilization
665F000	20	Each	Hay Bales
665J002	120	LF	Silt Fence
665O001	120	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 48,800.00)
701A231	15	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	27	Mile	Solid Temporary Traffic Stripe
703A002	270	SQFT	Traffic Control Markings, Class 2, Type A
705A032	115	Each	Pavement Markers, Class A-H, Type 1-B
705A037	828	Each	Pavement Markers, Class A-H, Type 2-D
740B000	222	SQFT	Construction Signs
740O000	1	Each	Pilot Car