

**Alabama Department of Transportation  
Proposal Item Summary**

---

**025. ACNU61231-ATRP(014) & ACNU61232-ATRP(014)**

**DEKALB COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 6.00

for constructing the Resurfacing and Traffic Stripe on CR-81 from the junction of CR-130 south of Fort Payne to the junction of CR-176 (Site #1) and on CR-83 from the junction of CR-55 to the intersection of CR-176 (Site #2). Length 3.265 mi.

The Bracket Estimate on this project is from \$429,269 to \$524,662.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
401B108	38,321	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	1,916	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	3,035	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	1,442	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
630A001	100	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 22,500.00)
701A231	8	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	7	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	1	Mile	Broken Temporary Traffic Stripe
701C001	7	Mile	Solid Temporary Traffic Stripe
703A002	380	SQFT	Traffic Control Markings, Class 2, Type A
705A032	50	Each	Pavement Markers, Class A-H, Type 1-B
705A037	381	Each	Pavement Markers, Class A-H, Type 2-D
740B000	367	SQFT	Construction Signs
740E000	25	Each	Cones (36 Inches High)
740O000	1	Each	Pilot Car