

**Alabama Department of Transportation  
Proposal Item Summary**

---

**037. ACOA62973-ATRP(012)**

**FRANKLIN COUNTY**

Contract Time: 45 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic Stripe on CR-56 from the intersection of SR-13 (US-43) to the junction of CR-60 in Russellville; on CR-48 from the junction of Clement Road to the Colbert County Line; and on County Line Road from the junction of CR-80 to the junction of CR-48. Length 8.571 mi.

The Bracket Estimate on this project is from \$805,239 to \$984,181.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
401A004	23,632	SQYD	Bituminous Treatment E
401B108	40,277	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	2,194	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
409A001	36,387	SQYD	Triple Layer Bituminous Treatment
424A340	1,645	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B635	4,027	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B670	350	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B047	394	Ton	Aggregate Surfacing (3/4" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 43,000.00)
701A030	18	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	14	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	4	Mile	Broken Yellow, Class 2T, Type A Traffic Stripe
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	14	Mile	Solid Temporary Traffic Stripe
705A032	133	Each	Pavement Markers, Class A-H, Type 1-B
705A037	993	Each	Pavement Markers, Class A-H, Type 2-D
740B000	479	SQFT	Construction Signs
740O000	1	Each	Pilot Car