

**Alabama Department of Transportation  
Proposal Item Summary**

---

**038. ACOA62974-ATRP(013)**

**FRANKLIN COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic Stripe on Walnut Gate Road from the intersection of SR-13 (US-43) to the intersection of SR-24 in Russellville. Length 1.786 mi.

The Bracket Estimate on this project is from \$430,484 to \$526,147.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$2.00 per set.

*The Principal Items of work are approximately as follows:*

| <b>Item No.</b> | <b>Quantity</b> | <b>Units</b> | <b>Description</b>  |
|-----------------|-----------------|--------------|---|
| 401A004         | 7,644           | SQYD         | Bituminous Treatment E  |
| 405A000         | 1,123           | Gal          | Tack Coat   |
| 407B000         | 2               | Mile         | Joint Sealant For Hot Mix Asphalt Pavement  |
| 408A052         | 14,813          | SQYD         | Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)   |
| 424A340         | 1,884           | Ton          | Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B        |
| 424B643         | 1,909           | Ton          | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B |
| 424B670         | 150             | Ton          | Superpave Bituminous Concrete Lower Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B   |
| 430B047         | 1,118           | Ton          | Aggregate Surfacing (3/4" Down, Crusher Run)  |
| 600A000         | 1               | LS           | Mobilization  |
| 698A000         | 1               | LS           | Construction Fuel (Maximum Bid Limited to \$ 23,000.00)   |
| 701A231         | 4               | Mile         | Solid White, Class 2, Type A Traffic Stripe   |
| 701A235         | 4               | Mile         | Solid Yellow, Class 2, Type A Traffic Stripe  |
| 701C001         | 12              | Mile         | Solid Temporary Traffic Stripe  |
| 703A002         | 176             | SQFT         | Traffic Control Markings, Class 2, Type A   |
| 703B002         | 137             | SQFT         | Traffic Control Legends, Class 2, Type A  |
| 705A005         | 235             | Each         | Pavement Markers, Class A, Type 2-D   |
| 740B000         | 485             | SQFT         | Construction Signs  |
| 740O000         | 1               | Each         | Pilot Car   |