

**Alabama Department of Transportation
Proposal Item Summary**

042. BR-1214(257)

CHOCTAW COUNTY

Contract Time: 80 Working Days

for constructing the Bridge Replacement on CR-23 (Ararat Road) over Little Tallawampa Creek. Length 0.010 mi.

The Bracket Estimate on this project is from \$250,558 to \$306,237.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$5.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206A000	1	LS	Removal Of Old Bridge, Station 9+98.45
214A000	482	CUYD	Structure Excavation
214B001	217	CUYD	Foundation Backfill, Commercial
502A000	44,215	LB	Steel Reinforcement
524A010	289	CUYD	Culvert Concrete
600A000	1	LS	Mobilization
610C001	160	Ton	Loose Riprap, Class 2
610D003	155	SQYD	Filter Blanket, Geotextile
665J002	500	LF	Silt Fence
665Q002	100	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 8,500.00).
740B000	141	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B