

**Alabama Department of Transportation  
Proposal Item Summary**

**046. IM-1059(360)**

**GREENE COUNTY**

Contract Time: 145 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, Traffic Stripe, and Bridge Raising on I-59 from the CR-20 Interchange in Lizzieville to the SR-14 Interchange in Eutaw. Length 6.906 mi.

The Bracket Estimate on this project is from \$7,857,866 to \$9,604,059.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$27.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4000.00 Per Acre) (Approximately 1 Acre)
206D001	2,338	LF	Removing Guardrail
206D002	79	LF	Removing Curb
206D003	68	LF	Removing Curb And Gutter
206D007	251	LF	Removing Concrete Flume
206D011	310	LF	Removing Fence
206E008	32	Each	Removing Guardrail End Anchor (All Type)
210A000	1,276	CUYD	Unclassified Excavation
210D021	4,352	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
305B077	1,367	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
405A000	48,231	Gal	Tack Coat
407B000	15	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A053	314,735	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410C000	1	Each	Contractor Retained Profilograph
410H000	1	Each	Material Remixing Device
423A003	21,812	Ton	Stone Matrix Asphalt Wearing Layer, 1/2" Maximum Aggregate Size
423B002	25,938	Ton	Stone Matrix Asphalt Binder Layer, 3/4" Maximum Aggregate Size
424A360	7,721	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B584	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL E
424B588	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL E
424B650	8,682	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B684	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B688	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B689	1,287	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	27	Mile	Scoring Bituminous Pavement Surface
520B000	1	LS	Raising Existing Bridge, Station 106+01.62
520B001	1	LS	Raising Existing Bridge, Station 214+49.09
534D000	26	Each	Cleaning Existing Drop Inlet
534E000	132	LF	Cleaning Existing Culvert (Less Than Or Equal To 48" Horizontal Opening)
534E001	5,279	LF	Cleaning Existing Pipe (Less Than Or Equal To 48" Horizontal Opening)
534F000	659	LF	Cleaning Existing Culvert (Greater Than 48" Horizontal Opening)

Item No.	Quantity	Units	Description
534F001	238	LF	Cleaning Existing Pipe (Greater Than 48" Horizontal Opening)
600A000	1	LS	Mobilization
629D000	8	Each	Bridge Guardrail Retrofit, Type IC
630A001	4,063	LF	Steel Beam Guardrail, Class A, Type 2
630C001	12	Each	Guardrail End Anchor, Type 8
630C003	9	Each	Guardrail End Anchor, Type 13
630C050	8	Each	Guardrail End Anchor, Type 20 Series
630C070	13	Each	Guardrail End Anchor, Type 10 Series
635A000	310	LF	Woven Wire Fence
654A001	9,038	SQYD	Solid Sodding (Bermuda)
665B001	7	Ton	Temporary Mulching
665J002	6,076	LF	Silt Fence
665O001	6,076	LF	Silt Fence Removal
666A001	3	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 413,000.00)
701A227	15	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	15	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	15	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,920	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	29	Mile	Broken Temporary Traffic Stripe
701C001	56	Mile	Solid Temporary Traffic Stripe
701G146	1,060	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G154	1,060	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
703A002	1,466	SQFT	Traffic Control Markings, Class 2, Type A
705A031	1,595	Each	Pavement Markers, Class A-H, Type 1-A
705A032	14	Each	Pavement Markers, Class A-H, Type 1-B
705A037	55	Each	Pavement Markers, Class A-H, Type 2-D
726A000	400	LF	Portable Concrete Safety Barriers, Type 6
726A001	40	LF	Portable Concrete Safety Barriers, Type 6-A
726D020	4	Each	Portable Impact Attenuator Assembly (Unidirectional, TL-2)
728A000	1	Each	Truck Mounted Impact Attenuator Unit
740B000	1,752	SQFT	Construction Signs
740D000	300	Each	Channelizing Drums
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2