

**Alabama Department of Transportation  
Proposal Item Summary**

---

**048. IM-IMD-I065(435)**

**SHELBY COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 6.00

for constructing the Concrete Flumes and Sinkhole Repairs of Backslope Benches on I-65 from north of the SR-119 Interchange (Exit 246) to south of the Valleydale Road Interchange (Exit 247) in Indian Springs. Length 0.473 mi.

The Bracket Estimate on this project is from \$1,759,675 to \$2,150,714.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$42.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
201B001	12	Acre	Selective Clearing
206C003	1,765	SQYD	Removing Concrete Flumes
210A000	13,826	CUYD	Unclassified Excavation
210D001	5,931	CUYD	Borrow Excavation (Loose Truckbed Measurement)
260A001	2,750	CUYD	Cement Mortar Flowable Backfill, Mix 2
430B050	153	Ton	Aggregate Surfacing(ALDOT#1)
600A000	1	LS	Mobilization
610C001	9,017	Ton	Loose Riprap, Class 2
610D003	4,742	SQYD	Filter Blanket, Geotextile
614A000	1,600	CUYD	Slope Paving
635A001	1,734	LF	Woven Wire Fence (Metal Posts)
650A000	2,170	CUYD	Topsoil
654A000	19,525	SQYD	Solid Sodding
665A000	12	Acre	Temporary Seeding
665B001	36	Ton	Temporary Mulching
665E000	5,805	SQYD	Polyethylene
665G000	375	Each	Sand Bags
665I000	338	Ton	Temporary Riprap, Class 2
665J002	13,004	LF	Silt Fence
665N000	500	Ton	Temporary Coarse Aggregate,ALDOT Number 1
665O001	13,004	LF	Silt Fence Removal
665Q002	2,040	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 99,000.00)
740B000	516	SQFT	Construction Signs
740D000	150	Each	Channelizing Drums
742A001	2	Each	Portable Changeable Message Sign, Type 2