

**Alabama Department of Transportation
Proposal Item Summary**

051. NH-0003(592)

ESCAMBIA COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-3 (US-31) from north of the intersection of old US-31 (MP 64.710) to the south end of the Burnt Corn Creek Bridge (MP 68.954) in East Brewton. Length 4.244 mi.

The Bracket Estimate on this project is from \$1,330,991 to \$1,626,767.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	15,904	Gal	Tack Coat
407B000	12	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	42,446	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	10,695	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	1,596	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B653	25	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	12	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	3,506	CUYD	Topsoil
652A100	9	Acre	Seeding
652C000	50	Acre	Mowing
656A010	9	Acre	Mulching
665B001	27	Ton	Temporary Mulching
665J002	500	LF	Silt Fence
665O001	500	LF	Silt Fence Removal
665Q002	100	LF	Wattle
666A001	9	Acre	Pest Control Treatment
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 75,000.00)
701A227	10	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	6,810	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe
701C001	19	Mile	Solid Temporary Traffic Stripe
703A002	2,208	SQFT	Traffic Control Markings, Class 2, Type A
703B002	494	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,117	SQFT	Temporary Traffic Control Markings
705A030	130	Each	Pavement Markers, Class A-H, Type 2-C
705A031	563	Each	Pavement Markers, Class A-H, Type 1-A
705A032	204	Each	Pavement Markers, Class A-H, Type 1-B

Item No.	Quantity	Units	Description
705A037	186	Each	Pavement Markers, Class A-H, Type 2-D
705A038	102	Each	Pavement Markers, Class A-H, Type 2-E
730H001	3,510	LF	Loop Wire
740B000	1,215	SQFT	Construction Signs
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit