

**Alabama Department of Transportation
Proposal Item Summary**

052. NH-0010(538)

PIKE COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Planing, Resurfacing, and Traffic Stripe on SR-10 from the intersection of SR-53 (US-231) to east of the junction of East Troy Terrace (MP 181.063) in Brundidge. Length 1.429 mi.

The Bracket Estimate on this project is from \$457,816 to \$559,552.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
405A000	2,265	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	30,199	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	3,171	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
600A000	1	LS	Mobilization
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 25,700.00)
701A227	3	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	2	Mile	Broken Temporary Traffic Stripe
701C001	9	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G242	1	LF	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
703A002	1,133	SQFT	Traffic Control Markings, Class 2, Type A
703B002	160	SQFT	Traffic Control Legends, Class 2, Type A
703D001	667	SQFT	Temporary Traffic Control Markings
703E001	137	SQFT	Temporary Traffic Control Legends
705A030	90	Each	Pavement Markers, Class A-H, Type 2-C
705A032	132	Each	Pavement Markers, Class A-H, Type 1-B
705A037	365	Each	Pavement Markers, Class A-H, Type 2-D
705A038	200	Each	Pavement Markers, Class A-H, Type 2-E
740B000	826	SQFT	Construction Signs
740C000	24	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit