

**Alabama Department of Transportation
Proposal Item Summary**

**055. NH-HSIP-0001(586)
RANDOLPH COUNTY**

Contract Time: 50 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-1 (US-431) from the beginning of the 4-Lane Section south of Wedowee (MP 192.623) to the south end of the bridge (MP 195.470). Length 2.847 mi.

The Bracket Estimate on this project is from \$1,242,763 to \$1,518,932.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	1,500	LF	Removing Guardrail
206E008	8	Each	Removing Guardrail End Anchor (All Type)
405A000	5,000	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	88,500	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	8,500	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	375	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B654	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B684	200	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	2,130	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	9	Mile	Scoring Bituminous Pavement Surface
430B043	400	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	460	SQYD	Filter Blanket, Geotextile
630A001	1,500	LF	Steel Beam Guardrail, Class A, Type 2
630C000	6	Each	Guardrail End Anchor, Type 10
630C003	2	Each	Guardrail End Anchor, Type 13
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	680	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 72,000.00)
701A227	7	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	6	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	4	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	4,335	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	9	Mile	Broken Temporary Traffic Stripe

Item No.	Quantity	Units	Description
701C001	24	Mile	Solid Temporary Traffic Stripe
703A002	8,115	SQFT	Traffic Control Markings, Class 2, Type A
703B002	315	SQFT	Traffic Control Legends, Class 2, Type A
703D001	3,288	SQFT	Temporary Traffic Control Markings
705A030	180	Each	Pavement Markers, Class A-H, Type 2-C
705A031	275	Each	Pavement Markers, Class A-H, Type 1-A
705A032	575	Each	Pavement Markers, Class A-H, Type 1-B
705A037	400	Each	Pavement Markers, Class A-H, Type 2-D
705A038	300	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,730	SQFT	Construction Signs
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit