

**Alabama Department of Transportation  
Proposal Item Summary**

**056. NH-HSIP-0005(543)**

**WILCOX COUNTY**

Contract Time: 60 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-5 from 0.22 miles north of the intersection of SR-10 in Pine Hill to the Marengo County Line. Length 9.958 mi.

The Bracket Estimate on this project is from \$2,173,566 to \$2,656,581.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D002	53	LF	Removing Curb
209A000	1	Each	Mailbox Reset, Single
210D001	1,585	CUYD	Borrow Excavation (Loose Truckbed Measurement)
212A000	1,025	STA	Machine Grading Shoulders
405A000	16,985	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	140,014	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	13,237	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424A370	650	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	3,984	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	20	Mile	Scoring Bituminous Pavement Surface
430B043	1,350	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
614A000	14	CUYD	Slope Paving
650A000	5,510	CUYD	Topsoil
652A100	15	Acre	Seeding
652C000	72	Acre	Mowing
656A010	15	Acre	Mulching
665B001	45	Ton	Temporary Mulching
665J002	4,000	LF	Silt Fence
665O001	4,000	LF	Silt Fence Removal
665Q002	1,200	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 116,000.00)
701A091	1	Mile	Solid White, Class W, Type A Traffic Stripe (5" Wide)
701A099	1	Mile	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701A227	20	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	12	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	7	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C002	13	Mile	Broken Temporary Traffic Stripe (Paint)

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
701C003	63	Mile	Solid Temporary Traffic Stripe (Paint)
701D009	1	Mile	Solid Traffic Stripe Removed (Tape)
703A002	552	SQFT	Traffic Control Markings, Class 2, Type A
703B002	24	SQFT	Traffic Control Legends, Class 2, Type A
703D002	532	SQFT	Temporary Traffic Control Markings (Paint)
703E002	48	SQFT	Temporary Traffic Control Legends (Paint)
705A030	32	Each	Pavement Markers, Class A-H, Type 2-C
705A032	253	Each	Pavement Markers, Class A-H, Type 1-B
705A037	954	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,817	SQFT	Construction Signs
740D000	25	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740I002	3	Each	Warning Lights, Type B
740M001	200	Each	Ballast For Cone
740O000	1	Each	Pilot Car