

**Alabama Department of Transportation  
Proposal Item Summary**

**063. STPAA-HSIP-0048(504)**

**RANDOLPH COUNTY**

Contract Time: 70 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-48 from the junction of SR-1 (US-431) in Wedowee to north of Main Street near Woodland. Length 9.271 mi.

The Bracket Estimate on this project is from \$3,052,543 to \$3,730,885.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206D001	25	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
209A000	6	Each	Mailbox Reset, Single
401B100	140,250	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	9,000	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	107,000	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
408A053	28,160	SQYD	Planing Existing Pavement (Approximately 2.10" Thru 3.0" Thick)
410C000	1	Each	Contractor Retained Profilograph
410H000	1	Each	Material Remixing Device
424A356	7,000	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A359	150	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/8" Maximum Aggregate Size Mix, ESAL Range C/D
424A360	600	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B650	13,400	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B661	290	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B684	500	Ton	Superpave Bituminous Concrete Lower Binder Layer, Patching, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B687	500	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B688	6,000	Ton	Superpave Bituminous Concrete Lower Binder Layer, Leveling, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	3,610	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	18	Mile	Scoring Bituminous Pavement Surface
430B043	4,200	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	330	SQYD	Filter Blanket, Geotextile
629E015	466	LF	Bridge Rail Retrofit, Type SC(CB)
630A001	375	LF	Steel Beam Guardrail, Class A, Type 2
630C003	4	Each	Guardrail End Anchor, Type 13
630C050	2	Each	Guardrail End Anchor, Type 20 Series
630C070	6	Each	Guardrail End Anchor, Type 10 Series
665A000	9	Acre	Temporary Seeding

Item No.	Quantity	Units	Description
665B001	27	Ton	Temporary Mulching
665G000	100	Each	Sand Bags
665J002	250	LF	Silt Fence
665O001	250	LF	Silt Fence Removal
665Q002	490	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 164,000.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	17	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	10	Mile	Broken Temporary Traffic Stripe
701C001	152	Mile	Solid Temporary Traffic Stripe
701G146	465	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	80	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	386	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H002	851	LF	Solid Traffic Stripe Removed (Tape)
701H007	80	LF	Broken Traffic Stripe Removed (Tape)
703A002	1,007	SQFT	Traffic Control Markings, Class 2, Type A
703B002	273	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,400	SQFT	Temporary Traffic Control Markings
705A032	150	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,025	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,506	SQFT	Construction Signs
740O000	1	Each	Pilot Car