

**Alabama Department of Transportation  
Proposal Item Summary**

**064. STPAA-HSIP-0055(511)**

**COVINGTON COUNTY**

Contract Time: 75 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-55 from the Yellow River (MP 10.366) to the junction of SR-15 in Andalusia. Length 13.181 mi.

The Bracket Estimate on this project is from \$2,645,279 to \$3,233,119.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$16.00 per set.

*The Principal Items of work are approximately as follows:*

| Item No. | Quantity | Units | Description   |
|----------|----------|-------|---|
| 206C010  | 436      | SQYD  | Removing Concrete Driveway  |
| 209A000  | 8        | Each  | Mailbox Reset, Single   |
| 209A001  | 4        | Each  | Mailbox Reset, Double   |
| 209A002  | 13       | Each  | Mailbox Reset, Multiple   |
| 210D021  | 917      | CUYD  | Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)  |
| 212A000  | 1,366    | STA   | Machine Grading Shoulders   |
| 405A000  | 16,241   | Gal   | Tack Coat   |
| 407B000  | 14       | Mile  | Joint Sealant For Hot Mix Asphalt Pavement  |
| 408B001  | 184,664  | SQYD  | Micro-Milling Existing Pavement(Approximatley 1.10" Thru 2.00" Thick)   |
| 410H000  | 1        | Each  | Material Remixing Device  |
| 424A361  | 17,865   | Ton   | Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D          |
| 424B655  | 200      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D     |
| 424B663  | 5,414    | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D |
| 424B701  | 200      | Ton   | Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" MAXimum Aggregate Size mix, ESAL Range C/D   |
| 428A001  | 27       | Mile  | Scoring Bituminous Pavement Surface   |
| 600A000  | 1        | LS    | Mobilization  |
| 650A000  | 2,586    | CUYD  | Topsoil   |
| 652A100  | 32       | Acre  | Seeding   |
| 652C000  | 85       | Acre  | Mowing  |
| 656A010  | 32       | Acre  | Mulching  |
| 659C002  | 450      | SQYD  | Erosion Control Product, Type S2  |
| 665A000  | 11       | Acre  | Temporary Seeding   |
| 665B001  | 32       | Ton   | Temporary Mulching  |
| 665J002  | 3,180    | LF    | Silt Fence  |
| 665O001  | 3,180    | LF    | Silt Fence Removal  |
| 665P005  | 4        | Each  | Inlet Protection, Stage 3 Or 4  |
| 665Q002  | 3,600    | LF    | Wattle  |
| 666A001  | 32       | Acre  | Pest Control Treatment  |
| 680A001  | 1        | LS    | Geometric Controls  |
| 698A000  | 1        | LS    | Construction Fuel (Maximum Bid Limited to \$ 138,530.00)  |
| 701A227  | 27       | Mile  | Solid White, Class 2, Type A Traffic Stripe (5" Wide)   |
| 701A230  | 10       | Mile  | Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)  |
| 701A244  | 12       | Mile  | Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)   |

| Item No. | Quantity | Units | Description  |
|----------|----------|-------|--|
| 701C000  | 35       | Mile  | Broken Temporary Traffic Stripe                        |
| 701C001  | 80       | Mile  | Solid Temporary Traffic Stripe                         |
| 701D007  | 1        | Mile  | Solid Traffic Stripe Removed (Paint)                   |
| 701D008  | 1        | Mile  | Solid Traffic Stripe Removed (Plastic)                 |
| 701D014  | 1        | Mile  | Broken Traffic Stripe Removed (Paint)                  |
| 701D015  | 1        | Mile  | Broken Traffic Stripe Removed (Plastic)                |
| 701G146  | 2,654    | LF    | Solid White, Class W, Type A Traffic Stripe (5"Wide)   |
| 701G154  | 2,654    | LF    | Solid Yellow, Class W, Type A Traffic Stripe (5" Wide) |
| 703A002  | 877      | SQFT  | Traffic Control Markings, Class 2, Type A              |
| 703D001  | 1,753    | SQFT  | Temporary Traffic Control Markings                     |
| 705A032  | 460      | Each  | Pavement Markers, Class A-H, Type 1-B                  |
| 705A037  | 1,082    | Each  | Pavement Markers, Class A-H, Type 2-D                  |
| 740B000  | 1,432    | SQFT  | Construction Signs                                     |
| 740E000  | 120      | Each  | Cones (36 Inches High)                                 |
| 740M001  | 120      | Each  | Ballast For Cone                                       |
| 740O000  | 1        | Each  | Pilot Car  |