

**Alabama Department of Transportation
Proposal Item Summary**

065. STPAA-HSIP-0063(504)

ELMORE COUNTY

Contract Time: 65 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-63 from the end of the 4-Lane Section (MP 6.700) in Eclectic to the Tallapoosa County Line. Length 9.610 mi.

The Bracket Estimate on this project is from \$2,446,746 to \$2,990,468.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
212A000	868	STA	Machine Grading Shoulders
401B100	156,750	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	13,000	Gal	Tack Coat
407B000	10	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	160,000	SQYD	Micro-Milling Existing Pavement(Approximatley 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A360	13,580	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	2,110	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	1,500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	3,550	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	19	Mile	Scoring Bituminous Pavement Surface
430B043	3,000	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610D003	335	SQYD	Filter Blanket, Geotextile
650A000	500	CUYD	Topsoil
652A100	9	Acre	Seeding
652C000	9	Acre	Mowing
654A000	250	SQYD	Solid Sodding
656A010	9	Acre	Mulching
659C002	500	SQYD	Erosion Control Product, Type S2
665A000	9	Acre	Temporary Seeding
665B001	27	Ton	Temporary Mulching
665F000	100	Each	Hay Bales
665G000	100	Each	Sand Bags
665J002	2,500	LF	Silt Fence
665O001	2,500	LF	Silt Fence Removal
665Q002	500	LF	Wattle
666A001	9	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 138,000.00)
701A227	19	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	15	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)

Item No.	Quantity	Units	Description
701A244	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701C000	4	Mile	Broken Temporary Traffic Stripe
701C001	100	Mile	Solid Temporary Traffic Stripe
701G146	4,943	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	2,472	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701H001	4,943	LF	Solid Traffic Stripe Removed (Plastic)
701H006	2,472	LF	Broken Traffic Stripe Removed (Plastic)
703A002	1,400	SQFT	Traffic Control Markings, Class 2, Type A
703B002	23	SQFT	Traffic Control Legends, Class 2, Type A
703D001	675	SQFT	Temporary Traffic Control Markings
705A032	210	Each	Pavement Markers, Class A-H, Type 1-B
705A037	1,000	Each	Pavement Markers, Class A-H, Type 2-D
740B000	1,592	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	300	Each	Cones (36 Inches High)
740M001	300	Each	Ballast For Cone
740O000	1	Each	Pilot Car