

**Alabama Department of Transportation  
Proposal Item Summary**

**067. STPAA-HSIP-0093(502) & STPAA-HSIP-0201(532)**

**PIKE COUNTY**

Contract Time: 55 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Resurfacing, and Traffic Stripe on SR-93 from the north Town Limits of Brundidge (MP 2.542) to the junction of SR-15 (US-29) in Banks (Site #1) and on SR-201 from the junction of the CSX Railroad/SR-93 to the junction of SR-15 (US-29) in Banks (Site #2). Length 7.302 mi.

The Bracket Estimate on this project is from \$1,720,924 to \$2,013,352.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$19.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
210D021	480	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	772	STA	Machine Grading Shoulders
405A000	9,597	Gal	Tack Coat
407B000	8	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	110,046	SQYD	Micro-Milling Existing Pavement(Approximatley 1.10" Thru 2.00" Thick)
410H000	1	Each	Material Remixing Device
424A341	2,161	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424A361	8,413	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B640	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	592	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B655	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B663	2,356	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B700	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
424B701	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" MMaximum Aggregate Size mix, ESAL Range C/D
428A001	15	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
650A000	1,313	CUYD	Topsoil
652A100	20	Acre	Seeding
652C000	68	Acre	Mowing
656A010	20	Acre	Mulching
659C002	420	SQYD	Erosion Control Product, Type S2
665A000	7	Acre	Temporary Seeding
665B001	20	Ton	Temporary Mulching
665G000	150	Each	Sand Bags
665J002	1,950	LF	Silt Fence
665O001	1,950	LF	Silt Fence Removal
665P005	15	Each	Inlet Protection, Stage 3 Or 4
665Q002	2,930	LF	Wattle
666A001	20	Acre	Pest Control Treatment

Item No.	Quantity	Units	Description
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 90,500.00)
701A227	16	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	10	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	5	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	659	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	15	Mile	Broken Temporary Traffic Stripe
701C001	57	Mile	Solid Temporary Traffic Stripe
701D007	2	Mile	Solid Traffic Stripe Removed (Paint)
701D008	2	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	2	Mile	Broken Traffic Stripe Removed (Paint)
701D015	2	Mile	Broken Traffic Stripe Removed (Plastic)
703A002	2,915	SQFT	Traffic Control Markings, Class 2, Type A
703B002	705	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,025	SQFT	Temporary Traffic Control Markings
703E001	1,572	SQFT	Temporary Traffic Control Legends
705A030	438	Each	Pavement Markers, Class A-H, Type 2-C
705A032	371	Each	Pavement Markers, Class A-H, Type 1-B
705A037	669	Each	Pavement Markers, Class A-H, Type 2-D
705A038	308	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,198	SQFT	Construction Signs
740C000	22	SQFT	Special Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	2	Each	Pilot Car