

**Alabama Department of Transportation  
Proposal Item Summary**

---

**074. STPNU-1714(253)**

**COLBERT COUNTY**

Contract Time: 30 Working Days

for constructing the Resurfacing and Traffic Stripe on CR-48 from the pavement joint south of Poplar Creek Loop North to the pavement joint South of the intersection of SR-157. Length 2.476 mi.

The Bracket Estimate on this project is from \$415,989 to \$508,432.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

<b>Item No.</b>	<b>Quantity</b>	<b>Units</b>	<b>Description</b>
401A006	33,422	SQYD	Bituminous Treatment G
405A000	894	Gal	Tack Coat
407B000	3	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A340	2,607	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	1,200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B047	1,079	Ton	Aggregate Surfacing (3/4" Down, Crusher Run)
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,300.00)
701A231	5	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	4	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	9	Mile	Solid Temporary Traffic Stripe
701G251	173	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	76	SQFT	Traffic Control Markings, Class 2, Type A
703B002	56	SQFT	Traffic Control Legends, Class 2, Type A
703D001	76	SQFT	Temporary Traffic Control Markings
705A032	196	Each	Pavement Markers, Class A-H, Type 1-B
705A037	131	Each	Pavement Markers, Class A-H, Type 2-D
740B000	311	SQFT	Construction Signs
740O000	1	Each	Pilot Car