

**Alabama Department of Transportation
Proposal Item Summary**

078. STPNU-3514 (255)

HOUSTON COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on Smithville Road from the intersection of SR-1 (US-231) to the junction of CR-33 and on CR-33 from the junction of Smithville Road to the intersection of SR-53 northwest of Cottonwood. Length 5.848 mi.

The Bracket Estimate on this project is from \$678,925 to \$829,797.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
401A006	75,154	SQYD	Bituminous Treatment G
405A000	2,255	Gal	Tack Coat
407B000	6	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A341	6,265	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range A/B
424B700	50	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range A/B
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 38,000.00).
701C000	3	Mile	Broken Temporary Traffic Stripe
701C001	8	Mile	Solid Temporary Traffic Stripe
740B000	477	SQFT	Construction Signs
740O000	1	Each	Pilot Car