

**Alabama Department of Transportation
Proposal Item Summary**

079. STPNU-5613(251)

RANDOLPH COUNTY

Contract Time: 30 Working Days

for constructing the Full Depth Reclamation, Resurfacing, and Traffic Stripe on CR-52 from the junction of CR-87 to the Georgia State Line. Length 2.700 mi.

The Bracket Estimate on this project is from \$427,345 to \$522,310.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	59	SQYD	Removing Concrete Driveway
302A000	35,404	SQYD	Full Depth Reclamation,
302B000	841	Ton	Portland Cement For Full Depth Reclamation
401A000	35,736	SQYD	Bituminous Treatment A
401B106	34,152	SQYD	Bituminous Treatment JG (With Polymer Additive)
430B043	1,045	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 23,400.00)
701A231	6	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	5	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	1	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
703A002	220	SQFT	Traffic Control Markings, Class 2, Type A
705A032	36	Each	Pavement Markers, Class A-H, Type 1-B
705A037	321	Each	Pavement Markers, Class A-H, Type 2-D
740B000	416	SQFT	Construction Signs
740F002	15	Each	Barricades, Type III
740I002	9	Each	Warning Lights, Type B
740O000	1	Each	Pilot Car