

**Alabama Department of Transportation  
Proposal Item Summary**

---

**017. ACBRZ61379-ATRP(014)**

**ETOWAH COUNTY**

Contract Time: 120 Working Days

DBE Goal Percent: 3.00

for constructing the Bridge Replacement on Fairview Cove Road over Bristow Creek south of Aurora. Length 0.213 mi.

The Bracket Estimate on this project is from \$924,355 to \$1,129,768.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 Per Acre) (Approximately 1 Acre)
209A000	2	Each	Mailbox Reset, Single
210A000	2,748	CUYD	Unclassified Excavation
210D001	17,641	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	175	CUYD	Structure Excavation
214B001	167	CUYD	Foundation Backfill, Commercial
230A000	12	RBST	Roadbed Processing
301A012	3,524	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,643	SQYD	Bituminous Treatment A
405A000	90	Gal	Tack Coat
424A340	170	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424A346	100	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	378	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	100	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	49,256	LB	Steel Reinforcement
524A010	342	CUYD	Culvert Concrete
535A001	48	LF	18" Side Drain Pipe
600A000	1	LS	Mobilization
610C001	986	Ton	Loose Riprap, Class 2
610D003	880	SQYD	Filter Blanket, Geotextile
619A002	4	Each	18" Roadway Pipe End Treatment, Class 1
630A021	200	LF	Steel Beam Guardrail, Class A, Type 2 (Steel Post)
630C070	4	Each	Guardrail End Anchor, Type 10 Series
635B002	2	Each	Gate, 20 Feet Wide
636A004	1,970	LF	Barbed Wire Fence, 4 Strands, 4 Feet High (Metal Post)
650B000	2,233	CUYD	Topsoil From Stockpiles
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665A000	2	Acre	Temporary Seeding
665B001	4	Ton	Temporary Mulching
665E000	260	SQYD	Polyethylene
665I000	50	Ton	Temporary Riprap, Class 2
665J002	2,160	LF	Silt Fence
665O001	2,160	LF	Silt Fence Removal
665Q002	200	LF	Wattle

Item No.	Quantity	Units	Description
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 47,000.00)
701A030	1	Mile	Solid White, Class 2T, Type A Traffic Stripe
701A034	1	Mile	Solid Yellow, Class 2T, Type A Traffic Stripe
703A002	20	SQFT	Traffic Control Markings, Class 2, Type A
703D001	20	SQFT	Temporary Traffic Control Markings
705A037	30	Each	Pavement Markers, Class A-H, Type 2-D
713A000	40	LF	Permanent Barricades
740B000	191	SQFT	Construction Signs
740F002	6	Each	Barricades, Type III
740I002	3	Each	Warning Lights, Type B