

**Alabama Department of Transportation  
Proposal Item Summary**

---

**018. ACBRZ61699-ATRP(011)  
CLEBURNE COUNTY**

Contract Time: 140 Working Days

DBE Goal Percent: 3.00

for constructing the Bridge Replacement and Approaches on CR-118 over Dynne Creek south of Arbacoochee. Length 0.150 mi.

The Bracket Estimate on this project is from \$852,754 to \$1,042,255.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$8.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
201A002	1 LS		Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00 PER ACRE)(APPROXIMATELY 1 ACRE)
206A000	1 LS		Removal Of Old Bridge, Station 15+08.13
210A000	5,439 CUYD		Unclassified Excavation
214A000	3,200 CUYD		Structure Excavation
214B001	820 CUYD		Foundation Backfill, Commercial
230A000	8 RBST		Roadbed Processing
301A012	1,867 SQYD		Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,867 SQYD		Bituminous Treatment A
424A340	147 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	258 Ton		Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	80 Ton		Aggregate Surfacing (1" Down, Crusher Run)
502A000	116,559 LB		Steel Reinforcement
524A010	581 CUYD		Culvert Concrete
600A000	1 LS		Mobilization
602A000	12 Each		Right Of Way Markers
610C001	488 Ton		Loose Riprap, Class 2
610D003	390 SQYD		Filter Blanket, Geotextile
630A001	300 LF		Steel Beam Guardrail, Class A, Type 2
630C050	4 Each		Guardrail End Anchor, Type 20 Series
665A000	1 Acre		Temporary Seeding
665B001	3 Ton		Temporary Mulching
665F000	50 Each		Hay Bales
665J002	1,800 LF		Silt Fence
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 43,000.00)
701G263	1,600 LF		Solid Yellow, Class 2, Type A Traffic Stripe
740B000	225 SQFT		Construction Signs
740F002	8 Each		Barricades, Type III
740I002	4 Each		Warning Lights, Type B