

**Alabama Department of Transportation  
Proposal Item Summary**

---

**021. ACOA60289-ATRP(014)**

**BIBB COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing, Traffic Stripe, and Pavement Markers on CR-58 (University Way) from the intersection of SR-5 to the junction of SR-25 in Brent. Length 1.137 mi.

The Bracket Estimate on this project is from \$404,541 to \$494,439.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$6.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C008	190	SQYD	Removing Concrete Median
206D002	1,858	LF	Removing Curb
210D021	189	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
301E008	75	Ton	Crushed Aggregate Base Course, Type B, Plant Mixed
405A000	2,350	Gal	Tack Coat
407B000	2	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A360	1,775	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	460	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B043	262	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
610C000	250	Ton	Loose Riprap, Class 1
610D003	364	SQYD	Filter Blanket, Geotextile
623A001	459	LF	Concrete Gutter (Valley)
623C003	1,858	LF	Combination Curb & Gutter, Type C (Modified)
650A000	215	CUYD	Topsoil
654A001	1,934	SQYD	Solid Sodding (Bermuda)
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	100	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 22,000.00)
701A231	3	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	3	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701B205	425	LF	Dotted, Class 2, Type A, Traffic Stripe
701C001	6	Mile	Solid Temporary Traffic Stripe
701E010	906	LF	Broken Temporary Traffic Stripe
701G240	906	LF	Broken White, Class 2, Type A Traffic Stripe
703A002	767	SQFT	Traffic Control Markings, Class 2, Type A
703B002	90	SQFT	Traffic Control Legends, Class 2, Type A
703D001	432	SQFT	Temporary Traffic Control Markings
705A030	63	Each	Pavement Markers, Class A-H, Type 2-C
705A032	132	Each	Pavement Markers, Class A-H, Type 1-B
705A037	156	Each	Pavement Markers, Class A-H, Type 2-D
705A038	66	Each	Pavement Markers, Class A-H, Type 2-E
740B000	452	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums

Item No.	Quantity	Units	Description
740E000	125	Each	Cones (36 Inches High)
740M001	125	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit