

**Alabama Department of Transportation
Proposal Item Summary**

022. ACNU60291-ATRP(005), ACNU60292-ATRP(015) & ACNU60294-ATRP(006)
BIBB COUNTY

Contract Time: 90 Working Days

DBE Goal Percent: 4.00

for constructing the Resurfacing and Traffic Stripe on CR-12 (Grey Hill Road) from 0.3 mile west of the junction of CR-282 west of Green Pond to the Shelby County Line (Site #1); on CR-9/CR-24 (Vance Road) from the Tuscaloosa County Line to the intersection of SR-5 in West Blocton (Site #2); and on CR-26 (Haysop Church Road) from the intersection of SR-6 (US-82) to the junction of CR-131 northwest of Eoline (Site #3). Length 12.744 mi.

The Bracket Estimate on this project is from \$2,511,220 to \$3,069,269.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$10.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206D001	350 LF		Removing Guardrail
206E019	8 Each		Removing Guardrail End Anchor (Type 10)
401B108	165,348 SQYD		Bituminous Treatment G (With Polymer Additive)
405A000	12,414 Gal		Tack Coat
407B000	14 Mile		Joint Sealant For Hot Mix Asphalt Pavement
424A340	16,567 Ton		Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	650 Ton		Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	1,250 Ton		Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B648	400 Ton		Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	7,335 Ton		Aggregate Surfacing (1" Down, Crusher Run)
600A000	1 LS		Mobilization
630A001	550 LF		Steel Beam Guardrail, Class A, Type 2
630C003	4 Each		Guardrail End Anchor, Type 13
630C050	12 Each		Guardrail End Anchor, Type 20 Series
665J002	2,400 LF		Silt Fence
665O001	2,400 LF		Silt Fence Removal
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 132,000.00)
701A030	3 Mile		Solid White, Class 2T, Type A Traffic Stripe
701A034	2 Mile		Solid Yellow, Class 2T, Type A Traffic Stripe
701A044	1 Mile		Broken Yellow, Class 2T, Type A Traffic Stripe
701A231	23 Mile		Solid White, Class 2, Type A Traffic Stripe
701A235	16 Mile		Solid Yellow, Class 2, Type A Traffic Stripe
701A245	6 Mile		Broken Yellow, Class 2, Type A Traffic Stripe
701C000	7 Mile		Broken Temporary Traffic Stripe
701C001	46 Mile		Solid Temporary Traffic Stripe
701G144	802 LF		Solid White, Class W, Type A Traffic Stripe
701G152	802 LF		Solid Yellow, Class W, Type A Traffic Stripe
703A002	898 SQFT		Traffic Control Markings, Class 2, Type A
703A004	68 SQFT		Traffic Control Markings, Class 2T, Type A
705A032	364 Each		Pavement Markers, Class A-H, Type 1-B
705A037	1,490 Each		Pavement Markers, Class A-H, Type 2-D
740B000	708 SQFT		Construction Signs

Item No.	Quantity	Units	Description
740O000	1 Each	Pilot Car	