

Alabama Department of Transportation
Proposal Item Summary

028. ACOA61156-ATRP(002)

BALDWIN COUNTY

Contract Time: 100 Working Days

DBE Goal Percent: 5.00

for constructing the Planing, Resurfacing, and Traffic Stripe on Fairhope Avenue from the intersection of Bancroft Street to the intersection of SR-181 in Fairhope. Length 2.609 mi.

The Bracket Estimate on this project is from \$909,215 to \$1,111,262.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$19.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	205	SQYD	Removing Concrete Sidewalk
206D003	36	LF	Removing Curb And Gutter
210A000	1,450	CUYD	Unclassified Excavation
301A012	140	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	55	SQYD	Bituminous Treatment A
405A000	3,810	Gal	Tack Coat
407B000	5	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	6,502	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	5,923	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	200	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B657	125	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B662	440	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B692	7	Ton	Superpave Bituminous Concrete Lower Binder Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
600A000	1	LS	Mobilization
610D003	1,000	SQYD	Filter Blanket, Geotextile
618A000	153	SQYD	Concrete Sidewalk, 4" Thick
618A002	161	SQYD	Concrete Sidewalk, 4" Thick (Includes Brick Paver)
623C003	489	LF	Combination Curb & Gutter, Type C (Modified)
641S500	9	Each	Valve Box Reset
645K500	23	Each	Manhole Frame And Cover Reset
650A000	3,155	CUYD	Topsoil
654A001	9,561	SQYD	Solid Sodding (Bermuda)
665A000	3	Acre	Temporary Seeding
665B001	9	Ton	Temporary Mulching
665E000	500	SQYD	Polyethylene
665F000	200	Each	Hay Bales
665G000	200	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	1,500	LF	Wattle

Item No.	Quantity	Units	Description
666A001	3 Acre		Pest Control Treatment
674A000	1,000 LF		Construction Safety Fence
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 48,000.00)
701A227	1 Mile		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	5 Mile		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A231	6 Mile		Solid White, Class 2, Type A Traffic Stripe
701A244	1 Mile		Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	969 LF		Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C002	2 Mile		Broken Temporary Traffic Stripe (Paint)
701C003	15 Mile		Solid Temporary Traffic Stripe (Paint)
703A002	3,813 SQFT		Traffic Control Markings, Class 2, Type A
703B002	225 SQFT		Traffic Control Legends, Class 2, Type A
703D002	256 SQFT		Temporary Traffic Control Markings (Paint)
705A030	67 Each		Pavement Markers, Class A-H, Type 2-C
705A032	111 Each		Pavement Markers, Class A-H, Type 1-B
705A037	348 Each		Pavement Markers, Class A-H, Type 2-D
705A038	77 Each		Pavement Markers, Class A-H, Type 2-E
730H001	1,200 LF		Loop Wire
740B000	1,162 SQFT		Construction Signs
740D000	50 Each		Channelizing Drums
740E000	130 Each		Cones (36 Inches High)
740M001	130 Each		Ballast For Cone
741C010	2 Each		Portable Sequential Arrow And Chevron Sign Unit