

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**044. IM-1065(449)**

**AUTAUGA COUNTY**

Contract Time: 30 Working Days

DBE Goal Percent: 4.00

for constructing the Planing, Resurfacing, and Traffic Stripe on I-65 from the Elmore County Line to just south of the SR-3 (US-31) Interchange (MP 186.000) north of Prattville. Length 4.418 mi.

The Bracket Estimate on this project is from \$1,472,600 to \$1,799,844.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$3.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
408B000	156,000	SQYD	Micro-Milling Existing Pavement(Approximately 0.00" Thru 1.00" Thick)
410H000	1	Each	Material Remixing Device
420A015	7,400	Ton	Polymer Modified Open Graded Friction Course
420B000	31,200	Gal	Open Graded Friction Course Tack Coat
424B285	100	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
600A000	1	LS	Mobilization
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 88,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,350	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	18	Mile	Broken Temporary Traffic Stripe
701C001	36	Mile	Solid Temporary Traffic Stripe
701F000	1,350	LF	Dotted Temporary Traffic Stripe
703A002	409	SQFT	Traffic Control Markings, Class 2, Type A
705A031	700	Each	Pavement Markers, Class A-H, Type 1-A
740B000	1,802	SQFT	Construction Signs
740D000	500	Each	Channelizing Drums
740E000	500	Each	Cones (36 Inches High)
740M001	500	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2