

**Alabama Department of Transportation
Proposal Item Summary**

006. ACBR59659-ATRP(005)

LIMESTONE COUNTY

Contract Time: 180 Working Days

DBE Goal Percent: 2.00

for constructing the Bridge Replacement and Approaches at various sites on CR-304 (Ragsdale Creek Road) over Ragsdale Creek northeast of Elkmont. Length 0.255 mi.

The Bracket Estimate on this project is from \$667,775 to \$816,169.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$11.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4,000.00) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 40+45.90
206A001	1	LS	Removal Of Old Bridge, Station 84+63.50
206D000	36	LF	Removing Pipe
210A000	422	CUYD	Unclassified Excavation
210D001	2,273	CUYD	Borrow Excavation (Loose Truckbed Measurement)
214A000	1,420	CUYD	Structure Excavation
214B001	156	CUYD	Foundation Backfill, Commercial
230A000	13	RBST	Roadbed Processing
301A012	2,890	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,890	SQYD	Bituminous Treatment A
405A000	175	Gal	Tack Coat
424A340	265	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	362	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	143	Ton	Aggregate Surfacing (1" Down, Crusher Run)
502A000	67,817	LB	Steel Reinforcement
524A010	460	CUYD	Culvert Concrete
535A078	16	LF	15" Side Drain Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610C001	1,057	Ton	Loose Riprap, Class 2
610D003	961	SQYD	Filter Blanket, Geotextile
619A100	2	Each	15" Side Drain Pipe End Treatment, Class 1
650A000	390	CUYD	Topsoil
652A100	1	Acre	Seeding
656A010	1	Acre	Mulching
665J002	2,747	LF	Silt Fence
665O001	2,747	LF	Silt Fence Removal
665Q002	180	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 34,000.00)
701E000	5,400	LF	Solid Temporary Traffic Stripe
701G249	2,700	LF	Solid White, Class 2, Type A Traffic Stripe
701G263	2,700	LF	Solid Yellow, Class 2, Type A Traffic Stripe
705A037	20	Each	Pavement Markers, Class A-H, Type 2-D
740B000	166	SQFT	Construction Signs

Item No.	Quantity	Units	Description
740F002	4	Each	Barricades, Type III
740I002	2	Each	Warning Lights, Type B