

**Alabama Department of Transportation
Proposal Item Summary**

010. ACBRZ60420-ATRP(003) & ACBRZ60421-ATRP(003)
RANDOLPH COUNTY

Contract Time: 160 Working Days

DBE Goal Percent: 2.00

for the constructing the Bridge Replacement and Approaches on CR-427 over a Branch off of Cohobadiah Creek (Site #1) and on CR-425 over Cohobadiah Creek (Site #2) north of Newell. Length 0.187 mi.

The Bracket Estimate on this project is from \$666,905 to \$815,107.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4000.00 Per Acre) (Approximately 2 Acres)
206A000	1	LS	Removal Of Old Bridge, Station 19+76.65
206A001	1	LS	Removal Of Old Bridge, Station 19+82.30
210A000	2,030	CUYD	Unclassified Excavation
214A000	1,676	CUYD	Structure Excavation
214B001	401	CUYD	Foundation Backfill, Commercial
231B001	328	Ton	Roadbed Stabilizing Material, ALDOT #467
502A000	105,768	LB	Steel Reinforcement
524A011	549	CUYD	Culvert Concrete (Cast In Place)
600A000	1	LS	Mobilization
610C001	552	Ton	Loose Riprap, Class 2
610D003	436	SQYD	Filter Blanket, Geotextile
650A000	301	CUYD	Topsoil
652A100	2	Acre	Seeding
656A010	2	Acre	Mulching
665F000	400	Each	Hay Bales
665J002	2,000	LF	Silt Fence
665O001	2,000	LF	Silt Fence Removal
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 17,800.00)
740B000	151	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B