

Alabama Department of Transportation
Proposal Item Summary

020. ACNU60425-ATRP(013)

RANDOLPH COUNTY

Contract Time: 30 Working Days

DBE Goal Percent: 3.00

for constructing the Resurfacing and Traffic Stripe on CR-51 from a point 895 feet north of the intersection of CR-59 in Woodland to the Cleburne County Line. Length 8.741 mi.

The Bracket Estimate on this project is from \$1,495,335 to \$1,827,632.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C010	8	SQYD	Removing Concrete Driveway
401B108	103,112	SQYD	Bituminous Treatment G (With Polymer Additive)
405A000	3,094	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
424A346	11,802	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B640	1,700	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B642	900	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424C351	425	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
430B043	3,000	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
665F000	65	Each	Hay Bales
665J002	650	LF	Silt Fence
665O001	650	LF	Silt Fence Removal
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 80,000.00)
701A231	18	Mile	Solid White, Class 2, Type A Traffic Stripe
701A235	15	Mile	Solid Yellow, Class 2, Type A Traffic Stripe
701A245	4	Mile	Broken Yellow, Class 2, Type A Traffic Stripe
701C000	7	Mile	Broken Temporary Traffic Stripe
701C001	29	Mile	Solid Temporary Traffic Stripe
701G251	1,000	LF	Solid White, Class 2, Type A Traffic Stripe (6" Wide) (Rumble Strip)
703A002	660	SQFT	Traffic Control Markings, Class 2, Type A
705A032	206	Each	Pavement Markers, Class A-H, Type 1-B
705A037	949	Each	Pavement Markers, Class A-H, Type 2-D
740B000	354	SQFT	Construction Signs
740O000	1	Each	Pilot Car