

Alabama Department of Transportation
Proposal Item Summary

033. BR-0214(251)

BALDWIN COUNTY

Contract Time: 120 Working Days

DBE Goal Percent: 5.00

for constructing the Bridge Replacement (Bridge Culvert) and Approaches on CR-55 over an Unnamed Branch of Polecat Creek west of Summerdale. Length 0.151 mi.

The Bracket Estimate on this project is from \$828,021 to \$1,012,026.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$13.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4000.00 Per Acre) (Approximately 1 Acre)
206A000	1	LS	Removal Of Old Bridge, Station 19+90
206D000	37	LF	Removing Pipe
206D001	278	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
210A000	1,443	CUYD	Unclassified Excavation
210D012	5,010	CUYD	Borrow Excavation (A-2-4(0) Or A-4(0))
214A000	398	CUYD	Structure Excavation
214B001	218	CUYD	Foundation Backfill, Commercial
230A000	8	RBST	Roadbed Processing
301A012	2,731	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	2,720	SQYD	Bituminous Treatment A
405A000	141	Gal	Tack Coat
424A360	233	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B651	420	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	10	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B659	10	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1" Maximum Aggregate Size Mix, ESAL Range C/D
430B040	15	Ton	Aggregate Surfacing (Crushed Aggregate Base, Type B)
502A000	64,178	LB	Steel Reinforcement
524A011	446	CUYD	Culvert Concrete (Cast In Place)
535A001	43	LF	18" Side Drain Pipe
600A000	1	LS	Mobilization
602A000	16	Each	Right Of Way Markers
610C001	562	Ton	Loose Riprap, Class 2
610D003	933	SQYD	Filter Blanket, Geotextile
619A101	2	Each	18" Side Drain Pipe End Treatment, Class 1
630A001	504	LF	Steel Beam Guardrail, Class A, Type 2
630C050	4	Each	Guardrail End Anchor, Type 20 Series
650A000	570	CUYD	Topsoil
652C000	1	Acre	Mowing
654A001	5,130	SQYD	Solid Sodding (Bermuda)
659C002	1,201	SQYD	Erosion Control Product, Type S2
665A000	2	Acre	Temporary Seeding

Item No.	Quantity	Units	Description
665B001	6 Ton		Temporary Mulching
665E000	2,000 SQYD		Polyethylene
665F000	150 Each		Hay Bales
665G000	150 Each		Sand Bags
665I000	60 Ton		Temporary Riprap, Class 2
665J002	400 LF		Silt Fence
665L000	305 LF		Floating Basin Boom
665N000	25 Ton		Temporary Coarse Aggregate,ALDOT Number 1
665N001	20 Ton		Temporary Coarse Aggregate,ALDOT Number 4
665O001	400 LF		Silt Fence Removal
665Q002	336 LF		Wattle
666A001	1 Acre		Pest Control Treatment
680A001	1 LS		Geometric Controls
698A000	1 LS		Construction Fuel (Maximum Bid Limited to \$ 42,600.00)
701E000	1,800 LF		Solid Temporary Traffic Stripe
701G253	1,800 LF		Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G265	1,800 LF		Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
705A037	23 Each		Pavement Markers, Class A-H, Type 2-D
740B000	373 SQFT		Construction Signs
740F002	10 Each		Barricades, Type III
740I002	5 Each		Warning Lights, Type B