

Alabama Department of Transportation
Proposal Item Summary

039. ERPR-8980(909)

BALDWIN COUNTY

Contract Time: 120 Working Days

DBE Goal Percent: 5.00

for constructing the Grade, Drain, Base, Pave, and Drainage Structure Replacements on CR-32 at various sites from the intersection of CR-73 to the junction of CR-83 in Summerdale. Length 0.173 mi.

The Bracket Estimate on this project is from \$733,627 to \$896,655.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$21.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
201A002	1	LS	Clearing And Grubbing (Maximum Allowable Bid \$ 4000.00) (Approximately 1 Acre)
206B000	1	LS	Removal Of Old Box Culvert, Station 31+16.78 - 31+44.04 on CR-32
206D000	267	LF	Removing Pipe
206D001	258	LF	Removing Guardrail
206E008	4	Each	Removing Guardrail End Anchor (All Type)
210A000	1,826	CUYD	Unclassified Excavation
210D022	467	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A-2-4(0) or A-4(0))
214A000	1,671	CUYD	Structure Excavation
214B001	320	CUYD	Foundation Backfill, Commercial
230A000	9	RBST	Roadbed Processing
301A012	2,158	SQYD	Crushed Aggregate Base Course, Type B, Plant Mixed, 6" Compacted Thickness
401A000	1,999	SQYD	Bituminous Treatment A
405A000	199	Gal	Tack Coat
424A340	220	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range A/B
424B636	273	Ton	Superpave Bituminous Concrete Upper Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
424B666	273	Ton	Superpave Bituminous Concrete Lower Binder Layer, 1" Maximum Aggregate Size Mix, ESAL Range A/B
502A001	42,156	LB	Steel Reinforcement (Grade 60)
524A011	246	CUYD	Culvert Concrete (Cast In Place)
530A007	67	LF	54" Roadway Pipe (Class 3 R.C.)
530B006	118	LF	59" Span, 36" Rise Roadway Pipe (Class 3 R.C.)
600A000	1	LS	Mobilization
610C001	480	Ton	Loose Riprap, Class 2
610D003	380	SQYD	Filter Blanket, Geotextile
619A058	2	Each	54" Roadway Pipe End Treatment, Class 2
619B286	2	Each	59" Span, 36" Rise Roadway Pipe End Treatment, Class 2 (Double Line)
630A001	408	LF	Steel Beam Guardrail, Class A, Type 2
630C050	8	Each	Guardrail End Anchor, Type 20 Series .
650A000	356	CUYD	Topsoil
654A001	2,737	SQYD	Solid Sodding (Bermuda)
665A000	3	Acre	Temporary Seeding
665B001	5	Ton	Temporary Mulching
665E000	6,000	SQYD	Polyethylene
665F000	450	Each	Hay Bales
665G000	450	Each	Sand Bags

Item No.	Quantity	Units	Description
665J002	1,750	LF	Silt Fence
665O001	1,750	LF	Silt Fence Removal
665Q002	840	LF	Wattle
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 41,100.00).
701E000	2,382	LF	Solid Temporary Traffic Stripe
701E010	644	LF	Broken Temporary Traffic Stripe
701G253	1,835	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701G256	644	LF	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701G265	548	LF	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
705A037	15	Each	Pavement Markers, Class A-H, Type 2-D
740B000	327	SQFT	Construction Signs
740F002	8	Each	Barricades, Type III
740I002	4	Each	Warning Lights, Type B
742A002	2	Each	Portable Changeable Message Sign, Type 1