

Alabama Department of Transportation
Proposal Item Summary

042. HSIP-0063(506)

TALLAPOOSA COUNTY

Contract Time: 35 Working Days

for constructing the Traffic Signal Upgrade on SR-63 at the intersection of Main Street in Alexander City.

The Bracket Estimate on this project is from \$160,856 to \$196,601.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206E022	2	Each	Removing Metal Pole With Light
600A000	1	LS	Mobilization
614A000	8	CUYD	Slope Paving
618A000	100	SQYD	Concrete Sidewalk, 4" Thick
623B000	60	LF	Concrete Curb, Type N
623B001	40	LF	Concrete Curb, Type N Special
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 5,000.00)
703A002	200	SQFT	Traffic Control Markings, Class 2, Type A
703C001	150	SQFT	Removal Of Existing Traffic Control Markings Or Legends (Plastic)
730A000	1	LS	Removal Of Existing Traffic Control Unit (SR-63 At Main Street)
730C000	1	LS	Furnishing And Installing Traffic Control Unit (SR-63 At Main Street)
730F000	1	Each	Metal Traffic Signal Pole With 40' MAST ARM ASSEMBLY
730F001	1	Each	Metal Traffic Signal Pole With 40' AND 45' MAST ARM ASSEMBLY
730K000	4	Each	Traffic Signal Junction Box
730L004	20	LF	2", Metallic, Conduit
730L005	100	LF	2", Non-Metallic, Conduit
730N000	2	Each	Luminaire Extension Assembly, 12 FEET
730P022	5	Each	Vehicular Signal Head, 12 Inch, 3 Section, Type LED
730P024	1	Each	Vehicular Signal Head, 12 Inch, 5 Section, Type LED
730R022	1	Each	Controller Assembly, Type III, 8 Phase
730T000	1	Each	Wood Pole
730U015	1	LS	Video Detection System
730Y600	1	LS	Furnishing And Installing Pedestal Pole And Foundation With LED Pedestrian Signal Head
730Y601	1	LS	Furnishing And Installing Pedestal Pole And Foundation With LED Pedestrian Signal Head
740B000	535	SQFT	Construction Signs
740D000	200	Each	Channelizing Drums
740E000	200	Each	Cones (36 Inches High)
740M001	200	Each	Ballast For Cone
741C010	1	Each	Portable Sequential Arrow And Chevron Sign Unit
756A028	200	LF	6" Electrical Conduit, 1 Line, Type 5 Installation