

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**052. NH-HSIP-0006(556)**  
**MONTGOMERY COUNTY**

Contract Time: 90 Working Days

DBE Goal Percent: 3.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-6 (US-82) from the junction of SR-8 (US-80) at MP 158.668 to a pavement joint just south of SR-271 (MP 162.272) and on the westbound lane only from MP 165.800 to MP 166.441. Length 4.244 mi.

The Bracket Estimate on this project is from \$3,162,276 to \$3,865,004.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$4.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
210D021	750	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
212A000	900	STA	Machine Grading Shoulders
305B077	300	Ton	Crushed Aggregate, Section 825, For Miscellaneous Use
401B100	116,000	SQYD	Bituminous Treatment E (With Polymer Additive)
405A000	15,000	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408B001	201,600	SQYD	Micro-Milling Existing Pavement(Approximately 1.10" Thru 2.00" Thick)
408B003	4,600	SQYD	Micro-Milling Existing Pavement (Approximately 2.10" thru 3.00" Thick)
410H000	1	Each	Material Remixing Device
424A281	22,000	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424A370	5,000	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B280	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range E
424B285	500	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range E
424B287	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 1/2" Maximum Aggregate Size Mix, ESAL Range E
424B293	1,600	Ton	Superpave Bituminous Concrete Upper Binder Layer, Widening, 1 1/2" Maximum Aggregate Size Mix, ESAL Range E
428A001	11	Mile	Scoring Bituminous Pavement Surface
600A000	1	LS	Mobilization
645K500	3	Each	Manhole Frame And Cover Reset
650A000	1,000	CUYD	Topsoil
652A100	4	Acre	Seeding
652C000	4	Acre	Mowing
654A000	250	SQYD	Solid Sodding
656A010	4	Acre	Mulching
659C002	250	SQYD	Erosion Control Product, Type S2
665A000	4	Acre	Temporary Seeding
665B001	12	Ton	Temporary Mulching
665F000	100	Each	Hay Bales
665G000	100	Each	Sand Bags
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	500	LF	Wattle

Item No.	Quantity	Units	Description
666A001	4	Acre	Pest Control Treatment
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 180,000.00)
701A227	9	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	9	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	9	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701B207	12,800	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	25	Mile	Broken Temporary Traffic Stripe
701C001	60	Mile	Solid Temporary Traffic Stripe
701G252	600	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	5,733	SQFT	Traffic Control Markings, Class 2, Type A
703B002	2,328	SQFT	Traffic Control Legends, Class 2, Type A
703D001	1,848	SQFT	Temporary Traffic Control Markings
705A030	100	Each	Pavement Markers, Class A-H, Type 2-C
705A031	600	Each	Pavement Markers, Class A-H, Type 1-A
730H001	12,000	LF	Loop Wire
740B000	1,590	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	650	Each	Cones (36 Inches High)
740M001	650	Each	Ballast For Cone
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	4	Each	Portable Changeable Message Sign, Type 2