

**Alabama Department of Transportation**  
**Proposal Item Summary**

---

**053. NH-HSIP-0008(582)**  
**MARENGO COUNTY**

Contract Time: 50 Working Days

DBE Goal Percent: 4.00

for constructing the Safety Widening, Planing, Resurfacing, and Traffic Stripe on SR-8 (US-80) from the Hale County Line (MP 46.417) west of Faunsdale to the Perry County Line (MP 53.820) in Uniontown. Length 7.402 mi.

The Bracket Estimate on this project is from \$1,888,640 to \$2,308,338.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$7.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
212A000	265	STA	Machine Grading Shoulders
405A000	21,000	Gal	Tack Coat
407B000	13	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	194,000	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A360	13,709	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424A369	366	Ton	Superpave Bituminous Concrete Wearing Surface Layer, Widening, 1/2" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	150	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424C370	1,010	Ton	Superpave Bituminous Concrete Base Layer, Widening, 1" Maximum Aggregate Size Mix, ESAL Range C/D
428A001	6	Mile	Scoring Bituminous Pavement Surface
430B043	500	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
650A000	800	CUYD	Topsoil
652A100	3	Acre	Seeding
652C000	65	Acre	Mowing
656A010	3	Acre	Mulching
665B001	9	Ton	Temporary Mulching
665J002	1,000	LF	Silt Fence
665O001	1,000	LF	Silt Fence Removal
665Q002	400	LF	Wattle
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 105,000.00)
701A227	30	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	22	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A239	10	Mile	Broken White, Class 2, Type A Traffic Stripe (5" Wide)
701A244	3	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	5,845	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	24	Mile	Broken Temporary Traffic Stripe
701C001	103	Mile	Solid Temporary Traffic Stripe
703A002	6,732	SQFT	Traffic Control Markings, Class 2, Type A
703B002	312	SQFT	Traffic Control Legends, Class 2, Type A
703D002	384	SQFT	Temporary Traffic Control Markings (Paint)
703E002	144	SQFT	Temporary Traffic Control Legends (Paint)
705A030	55	Each	Pavement Markers, Class A-H, Type 2-C

Item No.	Quantity	Units	Description
705A031	612	Each	Pavement Markers, Class A-H, Type 1-A
705A032	515	Each	Pavement Markers, Class A-H, Type 1-B
705A037	365	Each	Pavement Markers, Class A-H, Type 2-D
705A038	235	Each	Pavement Markers, Class A-H, Type 2-E
740B000	1,144	SQFT	Construction Signs
740D000	100	Each	Channelizing Drums
740E000	250	Each	Cones (36 Inches High)
740M001	250	Each	Ballast For Cone
740O000	1	Each	Pilot Car
741C010	2	Each	Portable Sequential Arrow And Chevron Sign Unit
742A001	2	Each	Portable Changeable Message Sign, Type 2