

**Alabama Department of Transportation  
Proposal Item Summary**

---

**056. SRTS-SR11(906)**

**LOWNDES COUNTY**

Contract Time: 30 Working Days

for constructing the Infrastructure Improvements (Sidewalks) on various routes at various locations in Fort Deposit as indicated in the plans.

The Bracket Estimate on this project is from \$138,709 to \$169,533.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$9.00 per set.

*The Principal Items of work are approximately as follows:*

Item No.	Quantity	Units	Description
206C000	50	SQYD	Removing Concrete Sidewalk
206D003	68	LF	Removing Curb And Gutter
210A000	210	CUYD	Unclassified Excavation
210D021	275	CUYD	Borrow Excavation (Loose Truckbed Measurement)(A4 or Better)
600A000	1	LS	Mobilization
618A000	1,926	SQYD	Concrete Sidewalk, 4" Thick
654A000	1,700	SQYD	Solid Sodding
665J002	1,500	LF	Silt Fence
665O001	1,500	LF	Silt Fence Removal
674A000	3,800	LF	Construction Safety Fence
680A001	1	LS	Geometric Controls
703A002	2,045	SQFT	Traffic Control Markings, Class 2, Type A
710A126	94	SQFT	Class 8, Aluminum Flat Sign Panels 0.08" Thick Or Steel Flat Sign Panels 14 Gauge (Type IX Background)
710B021	196	LF	Roadway Sign Post (#3 U Channel, Galvanized Steel or 2 ", 14 Ga Square Tubular Steel)
740B000	152	SQFT	Construction Signs
740D000	50	Each	Channelizing Drums
740E000	50	Each	Cones (36 Inches High)
740M001	50	Each	Ballast For Cone