

Alabama Department of Transportation
Proposal Item Summary

060. STPAA-0167(507)

GENEVA COUNTY

Contract Time: 40 Working Days

DBE Goal Percent: 5.00

for constructing the Resurfacing and Traffic on SR-167 from just north of the junction of SR-123 (MP 7.087) in Hartford to the Dale County Line. Length 8.774 mi.

The Bracket Estimate on this project is from \$1,609,027 to \$1,966,588.

A Bidding Proposal may be purchased for \$5.00. Plans may be purchased for \$12.00 per set.

The Principal Items of work are approximately as follows:

Item No.	Quantity	Units	Description
206C000	7	SQYD	Removing Concrete Sidewalk
206D002	12	LF	Removing Curb
405A000	12,794	Gal	Tack Coat
407B000	9	Mile	Joint Sealant For Hot Mix Asphalt Pavement
408A052	166,220	SQYD	Planing Existing Pavement (Approximately 1.10" Thru 2.0" Thick)
410H000	1	Each	Material Remixing Device
424A361	14,227	Ton	Superpave Bituminous Concrete Wearing Surface Layer, 3/4" Maximum Aggregate Size Mix, ESAL Range C/D
424B655	200	Ton	Superpave Bituminous Concrete Upper Binder Layer, Patching, 1" Maximum Aggregate Size Mix, ESAL Range C/D
424B701	300	Ton	Superpave Bituminous Concrete Upper Binder Layer, Leveling, 3/8" Maximum Aggregate Size mix, ESAL Range C/D
428A001	17	Mile	Scoring Bituminous Pavement Surface
430B043	28	Ton	Aggregate Surfacing (1" Down, Crusher Run)
600A000	1	LS	Mobilization
618A000	7	SQYD	Concrete Sidewalk, 4" Thick
680A001	1	LS	Geometric Controls
698A000	1	LS	Construction Fuel (Maximum Bid Limited to \$ 84,265.00)
701A227	18	Mile	Solid White, Class 2, Type A Traffic Stripe (5" Wide)
701A230	8	Mile	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701A244	8	Mile	Broken Yellow, Class 2, Type A Traffic Stripe (5" Wide)
701B207	1,755	LF	Dotted, Class 2, Type A Traffic Stripe (5" Wide)
701C000	32	Mile	Broken Temporary Traffic Stripe
701C001	16	Mile	Solid Temporary Traffic Stripe
701D007	1	Mile	Solid Traffic Stripe Removed (Paint)
701D008	1	Mile	Solid Traffic Stripe Removed (Plastic)
701D014	1	Mile	Broken Traffic Stripe Removed (Paint)
701D015	1	Mile	Broken Traffic Stripe Removed (Plastic)
701G146	2,099	LF	Solid White, Class W, Type A Traffic Stripe (5"Wide)
701G150	1,050	LF	Broken Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G154	1,050	LF	Solid Yellow, Class W, Type A Traffic Stripe (5" Wide)
701G252	600	LF	Solid White, Class 2, Type A Traffic Stripe (5" Wide) (Rumble Strip)
703A002	2,712	SQFT	Traffic Control Markings, Class 2, Type A
703B002	404	SQFT	Traffic Control Legends, Class 2, Type A
703D001	2,054	SQFT	Temporary Traffic Control Markings
705A030	330	Each	Pavement Markers, Class A-H, Type 2-C
705A032	450	Each	Pavement Markers, Class A-H, Type 1-B

Item No.	Quantity	Units	Description
705A037	675	Each	Pavement Markers, Class A-H, Type 2-D
705A038	150	Each	Pavement Markers, Class A-H, Type 2-E
740B000	979	SQFT	Construction Signs
740E000	150	Each	Cones (36 Inches High)
740M001	150	Each	Ballast For Cone
740O000	1	Each	Pilot Car